



Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola
Agriculture Research Station
Tharsa, Tq. Mauda, Dist. Nagpur- 441106

Dr. V. K. Biradar
Officer In-charge

E-mail(O) : arstharsa@pdkv.ac.in
arstharsa1910@gmail.com

No.ARS/Drain.Quot./123/2026

Date- 21/08/2026

Quotation Notice


Sealed quotations are invited for construction of Drainage channel at Agriculture Research Station, Tharsa for following specified items

Item No.	Particulars of Item	Qty.	Unit	Rate	Amount
1.	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR It. No. 21.02 /P.No. 148	15.55	Cum		
2.	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete. SSR It. No. 21.40 /P.No. 152	1.46	Cum		
3.	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR It. No. 24.01 /P.No. 169	0.97	Cum		
4.	Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR It. No. 25.11 /P.No. 172	2.24	Cum		
5.	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. slab as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum	1.46	Cum		

	thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete,(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR It. No. 25.70 /P.No. 182				
6.	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. pardi as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete,(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR It. No. 26.17 /P.No. 185	1.86	Cum		
7.	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. SSR It. No. 26.33 /P.No. 182	0.48	MT		
8.	Providing and fixing mild steel grill work for windows, ventilators, etc. 15 Kilogram/Square Metre as per drawing including fixtures necessary welding and painting with one coat of anticorrosive paint and two coats of oil painting complete SSR It. No. 40.02 /P.No. 253	89.10	Sqm		
		Total Rs.			

Terms and Conditions:

1. The quotations from authorised agencies should reach to this office on or before 31.08.2026 up to 5 pm for the above mentioned items.
2. The item number of particular work should be mentioned on the top of the envelope.
3. The rates should be quoted in figures and words clearly including all taxes (with GST) along with delivery charges at ARS, Tharsa
4. The right to reject any or all quotations or to call fresh quotations is reserved by the undersigned without assigning any reason there on.
5. The rates should be valid Upto March, 2027
6. Quotation received after the prescribed date will not be accepted.


 Officer Incharge
 21.08.26
 Agriculture Research Station
 Tharsa, Dist. Nagpur