



Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola
Agriculture Research Station
Tharsa, Tq. Mauda, Dist. Nagpur- 441106

Dr. V. K. Biradar
Officer In-charge

E-mail(O) : arstharsa@pdkv.ac.in
arstharsa1910@gmail.com

No.ARS/Pathway.Quot./124/2026

Date: 21.08.2026

Quotation Notice


Sealed quotations are invited for construction of Pathway at Agriculture Research Station, Tharsa for following specified items

Item No.	Particulars of Item	Qty.	Unit	Rate	Amount
1.	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means SSR It. No. 21.02 /P.No. 148	27.97	Cum		
2.	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete. SSR It. No. 21.40 /P.No. 152	7.99	Cum		
3.	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer in charge in layers of 15 cm to 20 cm including watering and compaction etc. complete. SSR It. No. 21.37 /P.No. 157	11.99	Cum		
4.	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR It. No. 24.01 /P.No. 169	7.99	Cum		
5.	Providing and laying in situ cement concrete M30 with tremix treatment for 200 mm thickness for flooring with groove cutting of 4mmwide and 20mm deepwith necessary refilling with bitumen etc. complete. SSR It. No. 33.31 /P.No. 216	79.90	Sqm		

6.	Providing and fixing in position TMT FE 500, 25 mm dia dowel bars precoated with anticorrosive epoxy paint of required Dia. 60 cms. Long and at 30.00 cm. C/C and wherever directed including handling, straightening, necessary cutting supported by TMT FE 500, chairs with proper alignment by using properly designed assembly of Bulk heads lubricating half-length with bituminous paint as directed etc. complete. SSR It. No. 5.15 /P.No. 43	135	Nos.		
Total Rs.					

Terms and Conditions:

1. The quotations from authorised agencies should reach to this office on or before 31.08.2026 up to 5 pm for the above mentioned items.
2. The item number of particular work should be mentioned on the top of the envelope.
3. The rates should be quoted in figures and words clearly including all taxes (with GST) along with delivery charges at ARS, Tharsa
4. The right to reject any or all quotations or to call fresh quotations is reserved by the undersigned without assigning any reason there on.
5. The rates should be valid Upto March, 2027
6. Quotation received after the prescribed date will not be accepted.


 Officer Incharge 21.08.26
 Officer Incharge
 Agriculture Research Station
 Tharsa, Dist. Magar