डॉ. पंजाबराव देशमुख कृषि विद्यापीठ, अकोला कृषि तंत्र विद्यालय, सावंगी

पो. उपरवाही, ता. कळमेश्वर, जि. नागपूर – ४४९५०९

मी. नं	848488538	९६ (प्राचार्य)
--------	-----------	------------------

ई-मेल आयडी: atssawangi@pdkv.ac.in

जा.क्र/क्.तं.वि/८२२ /2025

	गिवदा
प्रति,	

विषय: रेशीम कीटक संगोपनगृहाचे बांधकाम करण्याकरिता दर पुरविणेबाबत.

उपरोक्त विषयाच्या अनुषंगाने कळविण्यात रोते की, कृषि तंत्र विद्यालय, ता. कळमेश्वर, जि. नागपूर येशील प्रक्षेत्रावर रेशीम संगोपणगृहाचे कीटक (६.४७ मी. X ४.९७ मी.) आकारात्या शेडवे बांधकाम करावचाचे आहे. त्याकरिता आपणाकडून लिफाफा बंद दर निविदा मागविण्यात थेत आहे.

Sr.No.	Particulars	Quantity	Unit	Rate
1.	Excavation for foundation in earth, soil	8.39	Cum	
	of all types, sand, gravel and soft			
	murum, including removing the			
	excavated material up to a distance of			
	50 m beyond the building area and			
	stacking and spreading as directed,			
	dewatering. preparing the bed for the			
	foundation and necessary back filling,			
	ramming, watering including shoring			
	and strutting etc complete. (Lift upto			
	1.5 m.) By Manul			
2.	Filling in plinth and floors with	4.66	Cum	
	contractors material/brought from			
	outside and approved by Engineer			

	incharge in layers of 15 cm to 20cm	1	
	including watening and compaction	1	
	etc. complete		
3.	Providing and laying Cast in situ	3.62	Cum
	Ready Mix cement concrete in M-10 of	f	
	trap/ granite quartzite/ gneiss metal for		
	foundation and bedding including		
	bailing out water. Steel centering,		
	formwork, laying/pumping,		
	compacting. roughening them if		
	special finish is to be provided,		
	finishing if required and curing		
	complete, with fully automatic micro		
	processor based PLC with SCADA	1	
	enabled reversible Drum Type		
	mixer/concrete Batch mix plant (Pan		
	mixer) etc. complete. With fine		
	aggregate (Natural Sand/Crushed sand		
	VSI Grade finely washed etc)		
4.	Providing second class Burnt Brick	2.47	Cum
	masonry with conventional/ IS type		
	bricks in cement mortar 1.6 in		
	foundations and plinth of inner walls in		
	plinth external walls including bailing		
	out water manually, striking joints on		
	unexposed faces raking out joints on		
	exposed faces and watering etc.		
	Complete		
5.	Providing second class Bumt Brick	2.34	Cum
۶.	masonry with conventional/ 1.S. type		
	bricks in cement mortar 1-6 for super		
	structure of inner walls striking joints		
	on unexposed faces, raking out joints		
	on exposed faces and watering etc		
	Oil Capeers		

	Complete		
6.	Providing and laying Cast in situ	0.39	Cum
	Ready Mix cement concrete in M20 of		
	trap/ granite/quartzite/gneiss metal for		
	bed blocks, foundation blocks and such		
	other items including bailing out water,		
	Steel centering, formwork laying/		
	pumping, compacting, roughening		
	them if special finish is to be provided,		
	finishing uneven and honeycombed		
	surface and curing etc. complete. The		
	Cement Mortar 1:3 plaster is		
	considered for rendering uneven and		
	honeycombed surface only Newly laid		
	concrete shall be covered by gunny		
	bag, plastic, tarpaulin etc.		
7.	Providing internal cement plaster	60.76	Sqm
	20mm thick in Single coats in cement		
	mortar 1:5 without neeru finish, to		
	concrete brick surface, in all positions		
	including scaffolding and curing etc		
	complete		
8.	Providing structural steel work of	0.94	mt
	rectangular hollow steel section for		
	steel trusses, other similar trussed		
	items like purlin and members with all		
	bracing, gusset plates etc. as per		
	detailed designs and drawings or as		
	directed including cutting, fabricating,		
	boisting, erecting, fixing in position		
	making riveted/bolted/ welded		
	connections and one coat of		
	anticorrosive paint and over it two		
	coats of oil painting of approved		

	quality and shade complete			
9.	Providing and fixing colour coated	38.64	Sqm	
	Zincalume profiled sheets for roofing.			
	The feed material is manufactured out			
	of nominal 0.45 mm Base Metal			
	Thickness steel quality super durable			
	polyester paint coat Including fasteners			
	with min., self-drilling screw etc.			
	complete. (weight of profile 4.52			
	Kilogram/Square Metre)			
10.	Providing and fixing colour coated	7.00	Rmt	
	Zincalume profiled plain sheets for			
	ridge on roofing. The feed material is			
	manufactured out of nominal 0.45 mm			
	Base Metal Thickness steel quality			
	super durable polyester paint coat			
	Including fasteners with min., self-			
	drilling screw etc. complete. (weight of			
	profile 4.52 Kilogram/Square Metre)			
11.	Providing and applying three coats of	60.76	Sqm	
	water proof cement paint of approved		1	
	manufacture and of approved colour to			
	old plastered surfaces including			
	scaffolding if necessary, cleaning and			
	preparing the surface, watering for two			
	days etc. complete.			
12.	Proiding & fixing in position Chainlink	45.52	Sqm	
	fencinf having size50x50 of 10		oqin	
	gaugefix on M. s pipe & over 35x4			
	mm mis flat with welding etccomplete.			

नियम व अटी:

१. सिलबंद निवीदा24 /11/2025 या तारखेट्या आत पोहयवयास पाढीजे निवीदा उशीरा पोहचल्यास त्या निवीदाचा विचार करण्यात रोणार नाढी.

- २ तिफाप्यावर निवीदा **रेशीम किटक संगोपनगृह बांधकामाचे दर** असा उल्लेख करावा.
- ३. कामे समाधानकारक झाली नसल्यास सदर कामे पुन्हा करून द्यावे लागेल सूचना करून असे काम न केल्यास याबाबत मोबदला दिला जाणार नाही.
- ४. निवीदा स्विकारण्याचा किंवा नस्विकारण्याचा हक्क प्राचार्य, कृषि तंत्र विद्यालय, सावंगी यांचे कडे राखून ठेवलेला आहे.
- फाम वेळेत पूर्ण करावे लागेल काम अर्धवट सोडून दिल्यास सदस्वे कामाचे देयक अदा
 करण्यात रोणार नाही.
- इ. काम करीत असताना कोणत्याही प्रकारचे नुकसान, जिवीतहानी अथवा अपघात झाल्यारा कार्यात्य, विद्यापीठ अथवा संबंधित अधिकारी किंवा कर्मचारी जबाबदार सहणार नाही. त्याची सर्वस्वी जबाबदारी मालकाची व काम करणाऱ्याची सहीत.
- ७. काम करीत असतांना प्रक्षेत्रावर विद्यापीठाच्या मालमतेचे कोणत्याही प्रकारचे नुकसान होणार नाही याची कटाक्षाने काळजी ध्यावी. नुकसान झाल्यास मालकास जबाबदार धरण्यात येवून नुकसान भरपाई करण्यात येईल.
- ८. दरपत्रक सादर करताना दरांचा सर्व कर व सेवा शुल्कसहीत स्पष्ट उल्लेख करावा नमुद केलेल्या दराव्यतीरीक्त कोणतेही शुल्क अदा केल्या जाणार नाही. खोडतोड असलेले दरपत्रक रिवकारल्या जाणार नाही व तसे दरपत्रक रदद करण्यात येईल
- ९. काम समाधानकारक व पूर्ण झाल्यावर देयकाची संपूर्ण प्रक्रिया झाल्यावरच देयक स्वर्च अदा करण्यात रोईल.
- १०. पुरवठादार / कंत्राटदार हा अधिकृत / विहीत परवानाधारकच असावा.
- ११. पुरवठादार / कंत्राटदार GST परवानाधारक असावा. निविदा सादर करतांना निविदेवर GST क्रमांक नमुद्र करण्यात यावा.
- १२. काम झाल्यावर सदरचे केलेल्या कामांचे देयक दोन प्रतीत विनाविलंब शादर करावे देयकासोबत आपले बँक खाते क्रमांक पूर्ण माहितीसह सादर करावे.
- १३. आपण पूरवीत असलेले सर्व कामांचे दर हे आर्थिक वर्ष २०२७-२०२६ दरम्यान वैध राहतील. मध्यंतरीच्या कालावधित कोणत्याही प्रकारची महागाई व दरांमध्ये इतर कोणतेही बदल झाल्यास सादर केलेल्या दरांमध्ये बदल करता येणार नाही.
- १४. आपण करीत असलेले काम हे पूर्णताः अस्थाई स्वरूपाचे असेल या बाबत कोणताही स्थाई स्वरूपाचा दावा करता येणार नाही.

उपरोक्त प्रमाणे सर्व अटी व शर्ती मान्य असणाऱ्या पुरवठादार व काम धारकांनीच दरपत्रक सादर करावेत.

