



Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola
Agriculture Research Station
Tharsa, Tq. Mauda, Dist. Nagpur- 441106

Dr. V. K. Biradar
Officer In-charge

E-mail(O) : arstharsa@pdkv.ac.in
arstharsa1910@gmail.com

No.ARS/Farm.Rd./486/2026

Date- 30/01/2026


Quotation Notice

Sealed quotations are invited for strengthening of existing Farm Roads (5000 x 3.30 x 0.10 m = 1650 cum) (L,B,D) at Agriculture Research Station, Tharsa with following details.

Item No.	Particulars of Item	Qty.	Unit
1	Supplying soft murum at the road site, including conveying and stacking complete.	1650	Cum
2	Spreading hard murum / soft murum/ gravel or kankar for side width complete	1650	Cum
3	Compacting the sub grade / gravel /size metal (100 mm loose layers for all widths with Power roller having weight 8 to 10 MT including necessary labour, materials and artificial watering complete.	1650	Cum

Terms and Conditions:

1. The quotations from authorised agencies should reach to this office on or before 07.01.2026 up to 5 pm for the above mentioned items.
2. The rates should be quoted in figures and words clearly including all taxes (with GST) along with delivery charges at ARS, Tharsa
3. The right to reject any or all quotations or to call fresh quotations is reserved by the undersigned without assigning any reason there on.
4. The rates should be valid Upto March, 2027
5. Quotation received after the prescribed date will not be accepted.


Officer Incharge
Officer Incharge
Agriculture Research Station
Tharsa, Dist. Nagpur

Proforma

Quotation for 'Strengthening of existing Farm Roads'

To,
The Officer Incharge
Agriculture Research Station, Tharsa
Dist. Nagpur 441106

Subject: Quotation for the rates for 'Strengthening of existing Farm Roads' at ARS, Tharsa
Ref.: No.ARS/ Farm.Rd./486/2026 Date- 30/01/2026

Item No.	Particulars of Item	Qty.	Unit	Rate / Cum	Amount
1.	Supplying soft murum at the road site, including conveying and stacking complete.	1650	Cum		
2.	Spreading hard murum / soft murum/ gravel or kankar for side width complete	1650	Cum		
3.	Compacting the sub grade / gravel /size metal (100 mm loose layers for all widths with Power roller having weight 8 to 10 MT including necessary labour, materials and artificial watering complete.	1650	Cum		
	Total				
	GST 18 %				

Total Amount including all taxes (in words):

Signature and Date:

Name & Address:

Mobile No.:

GST No.: