



CENTRAL RESEARCH STATION

Dr. PANJABRAO DESHMUKH KRISHI VIDYAPEETH, AKOLA (M.S.) 444 104

E mail- directorcrs78@gmail.com

Phone (0724) 2258119

No/CRS/Gen/328/2017

Date: 29 / 06 / 2017


Quotation Notice

Subject -: New Three Phase Electric Connection (work along with material) at Central Research Station, Dr. PDKV, Akola by calling quotation reg.

Please arrange to send quotation for New Three Phase Electric Connection (work along with material) at Central Research Station, Dr. P.D.K.V., Akola with particulars and conditions as mentioned below. The details of works & materials are given in table enclosed here with form of quotation.

1. Quotation/estimate will be considered only for the specifications given (Form attached)
2. The quotation should be filled only by the **Licensed Electric contractor**.
3. Quotation should be submitted along with the valid license copy for doing such electrical works issued by Competent Authority
4. The work should be carried out as per the Esst. Under the supervision of concerned M.S.E.D.C. Ltd authority.
5. Any damages or any failures of equipments during the testing and commissioning will have to be borne by contractor & he will have to replace the equipment/materials at their own cost.
6. This office will not take any responsibility for accident to any person labour during the erection testing and commissioning of equipment and contractor will have to comply the court cases pay compensation as per rules
7. Contractor will have to provide sufficient firefighting equipment as per specification of the company & I.E. rule where necessary.
8. All the work shall be carried out only by the licensed electrical contractor. The name and license no and validity of the same should be intimated before commencement of the work.
9. All the tools and plants etc. are to be arranged by the contractor.
10. Stationary permission where ever required shall be obtained by the contractor.
11. **Also the material required to be procured will be of good quality and reputed make and conforming to the ISI standard and strictly as technical specification of company & same shall be get approved from concerned E.E. before utilization works.**
12. Executive Engineer MSEDCL will be final authority to give decision regarding any dispute which will be binding on contractor.
13. Final permission of electrical inspector should be obtained by the contractor after completion of work.
14. Other terms and condition applicable time to time as per Director, CRS, Dr.PDKV; Akola decision will be binding.
15. The contract will be terminated if the material of the quality and the work is not carried out satisfactory. In this case contractor will not be entitled for any reimbursement for the expenditure he has made.
16. Approval shall be obtained from MSEDCL for commissioning of infrastructure proposed in the estimate.
17. Original purchase receipts of material utilized at the site shall be submitted with W.C.R.
18. The quotation should be given in the form enclosed only.

19. The quotation should be in the name of Director of Farms, Central Research Station, Dr. P.D.K.V., Akola, by mentioning "New Three Phase Ag. Electric Connection (work along with material)" on sealed envelop.
20. The quotation should reach to this office on or before 20.07.2017.
21. The quotation will be accepted on all working days between 10.30 a.m. to 5.30 p.m. and will be opened on the last date of receiving quotation at 4.30 pm. or on next day.
22. The rate should be quoted inclusive of all taxes F.O.R. at Central Research Station, Dr. P.D.K.V., Akola
23. The rates quoted should remain valid for a period of 6 months from the date of opening the quotation.
24. The right to accept whole or part of the quotation or reject is reserved with undersigned without assigning reason therefore
25. Agreement between undersigned, MSEDCL & contractor may be executed prior to execution of the work regarding the quality of material, Method of construction, guarantee period, execution of work etc.
26. The work along with the materials should be completed as per work order within 15 days from the date of work order.
27. **The material mentioned in the work order should be get verified from Executive Engineer (ADMN) Circle Office before execution of work by the contractor himself.**
28. **The work should be done as per the specification given by Executive Engineer (ADMN). Circle office will be the Nodal Officer. He will ensure the source of material utilized, quality of material as well as method of construction.**
29. This office will not be responsible if the differential amount if any due to change in cost data or due to change in estimate during pendency of the work.
30. The bills with printed Bill No. and Sale tax No., VAT, TIN/ GST numbers will be accepted only.
31. Final payment of items will be made only after completion of work along with material and after the completion of the entire official formalities.
32. For any further details of quotation contact to the office of Director of Farms, Central Research Station, Dr. P.D.K.V., Akola during office time only.
33. Suitable agreement shall be executed with the contractor on the bond paper regarding above terms and condition.



Director
Central Research Station
Dr.P.D.K.V, Akola

FORM OF QUOTATION

Quotations for 'New Three Phase Electric Connection (work along with material)' for giving power supply to 1 No. of 3 phase AG connection of load 5 HP in r/o Director, Central Research Station, Dr. PDKV, Survey No. 48, Behind CRS workshop, Akola . FCC-7 as per the enquiry of the Central Research Station, Dr.P.D.K.V, Akola. The abstract of sanctioned work is as below

SN	Name	Gat No.	Village	Taluka/ S-Dn	Load in HP	Provision
1.	Director, Central Research Station, Dr. PDKV, Akola	48	Gudadhi	Akola	5	0.36 KM LT (1.3% Sup charges) for energising Ag pump

Item Code No. 1423

L. T. LINE 3 ph 4 W on 125 x 70 mm, 9m RSJ Pole with ANT for Phase & GNAT for neutral

Sr. No.	Description of Materials	Unit	Qty	RT/Unit (Rs)	Amount (Rs.)
1.	RSJ 125x70, 9 m long	No.	07		
2.	AAC Ant	Rmt	1080		
3.	AAC Gnat	Rmt	360		
4.	M. S. Flat 50 x 6 mm	Kg	49		
5.	L.T. Shackle insulator	No.	28		
6.	L.T. Shackle hardware	Pair	28		
7.	Earthing Sets L.T.	No.	07		
8.	L. T. Stay sets	No.	02		
9.	G.I. Stay Wire 7/3. 15 mm (10SWG)	Kg	20		
10.	Stay Insulators	No.	02		
11.	G.I. Wire 8 SWG/6 SWG	Kg	35		
12.	Concreting ration 1:4:8	Cmt	07		
13.	Sundries such as N/B, Washers, Welding etc.	LS	04		
	Total cost of material (A)				
14.	Labour charges				
	Sub Total I				
15.	1.3 % Sup. Charges in Sub Total I				
16.	Service tax @ 15% on 1.3 % Sup charge				
	Total cost of Estimate in Rs.				

The conditions in the quotation notice are accepted by me

Place :

Date :

**Signature of the Contractor
& Seal of the firm with licensed No.**