



CENTRAL RESEARCH STATION

Dr. PANJABRAO DESHMUKH KRISHI VIDYAPEETH, AKOLA (M.S.) 444 104

E mail- directorcrs78@gmail.com

No/CRS/Dev/ 196 /2025

Dt. 06/05/2025

Quotation Notice

Subject:- Quotaion for digging new well at Central Research Station, Dr. PDKV, Akola

Please arrange to send quotation for **digging of new well at Central Research Station, Dr. PDKV, Akola** with particulars and conditions as mentioned below. The details of works are given in table enclosed here with the form of quotation.

1. The Quotation should be given in the form enclosed.
2. Rates should be quoted as per work specified.
3. **Item specification of work should not be deviated from as mentioned in quotation.**
4. **Comparision will be done on final estimated cost only**
5. The quotation should be in the name of Director of Farms, Central Research Station, Dr. P.D.K.V., Akola, mentioned "**Rate for Digging of New Well**" on envelop.
6. The quotation should reach to this office on or before **13.05.2025**
7. The quotation will be accepted on all working days between 10.30 a.m. to 5.30 p.m. and will be opened on the next day.
8. GST number should be mentioned on quotation.
9. Clearly mention whether rates are inclusive or exclusive of GST.
10. No labours will be provided by this office.
11. This office will not be responsible if any accident happens during the renovation work.
12. While working, if there is damage to univ. property, the responsibility should be held on contractor.
13. **No payment will be done for incomplete work.**
14. The rates quoted should remain valid for a period of 1 year from the date of opening the quotation.
15. The right to accept whole or part of the quotation or reject is reserved with undersigned without assigning reason thereof.
16. The bills with printed Bill No. and GST numbers will be accepted only.
17. Final payment of work will be made only after complete work and after the completion of entire official formalities.
18. For any further details of quotation contact to the office of Director of Farms, Central Research Station, Dr. P.D.K.V., Akola during office time only.

Director
Central Research Station
Dr. P.D.K.V, Akola

FORM OF QUOTATION

Quotation for **Digging of New Well (20 ft. dia. x 50 ft. depth)** at Central Research Station, Dr. PDKV, Akola is as under.

SN	Item	Qty	Rate Rs. Per Unit	Amount Rs.
1	Excavation for foundation in earth, soil of all types and gravel and soft Murum, including removing the excavated material up to distance of 50 m. Beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. Complete. (lift up to 0.00 1.50 m.) by manual means 21.01	25.12 Cum.		
2	Excavation for foundation in hard Murum including removing excavated material up to distance of 50 m beyond building area and stacking and spreading as directed, dewatering preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. Complete. (lift up to 0.00 1.50 m.) by manual means (21.05)	75.36 Cum		
3	Excavation for foundation in hard Murum including removing excavated material up to distance of 50 m beyond building area and stacking and spreading as directed, dewatering preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. Complete. (lift from 1.5 to 3.0 m) by mechanical means (21.08)	50.24 Cum		
4	Excavation for foundation in soft rock and old cement or lime masonry foundations including removing the excavated material up to a distance of 50 m beyond building area and stacking as directed, including dewatering preparing the bed for the foundation and necessary back filling with available earth / murum. ramming, watering including shoring and strutting etc. Complete. (lift upto 1.5 m) by mechanical means (21.14)	200.96 Cum		
5	Excavation for foundation in hard rock by blasting including trimming and leveling the bed by chiseling where necessary and removing the excavated material and stacking it in measurable heaps within a distance of 50 m from the building area including dewatering and back filling with available earth / murum. ramming, watering etc. Complete. (lift upto 1.5 m) by mechanical means (21.17)	192.32 Cum		
6	Excavation for foundation in hard rock by blasting including trimming and leveling the bed by chiseling where necessary and removing the excavated material and stacking it in measurable heaps within a distance of 50 m from the building area including dewatering and back filling with available earth / murum. ramming, watering etc. Complete. (lift from 1.5 to 3.0 m) by mechanical means (21.18)	115.39 Cum		
7	Dewatering on BHP basis by using water pump including diversion of stream, providing cofferdams bunds etc. And other parts of the works and pumping out water during and after excavation as maybe required by using 3.0 BHP pump etc. Complete (prior approval of Superintending Engineer will be necessary) (12.22)	120.00 Cum		
	Total Amount Rs.			
	GST			
	Grand Total Rs.			

The conditions in the quotation notice are accepted by me.

Place :
Date :

Signature of the Supplier
& Seal of the firm