



## CENTRAL RESEARCH STATION

Dr. PANJABRAO DESHMUKH KRISHI VIDYAPEETH,  
AKOLA (M.S) 444 104

### CENTRAL STORE DEPARTMENT

**E-mail :** directorcrs78@gmail.com

**Phone (0724)2258119**

No. Dir.CRS/Store/688/2024

Date: 07.08.2024

### Quotation Notice

To,

1)

2)

3)

**Subject:** To supply rate quotations for renovation & colouring to office building of Central Store at Central Research Office Dr. PDKV, Akola .....reg.

You are requested to supply the rate quotations on or before **14.08.2024 upto 4.00 P.M.** in the name of **Director, Central Research Station, Dr. PDKV, Akola** for following materials as mentioned below:

#### Particulars of supply of material


SN	Item	Unit	Quantity	Rate
1	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc. complete as directed	Sqm	657.59	
2	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete	Sqm	310.64	
3	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface. etc. complete	Sqm	310.64	
4	Providing and applying two coats of synthetic enamel paint of approved colour to new /old structural steel work and wood work in buildings, including scaffolding if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.	Sqm	83.00	

5	Providing and applying two coats of exterior acryallic emulsion paint confirming to corresponding I.S. of approved manufacture and of approved colour to the plastered surfaces including cleaning ,preparing the plaster surface, applying primer coat ,scaffolding if necessary , and watering the surface for two days etc complete.	Sqm	346.95	
6	Providing & Fixing pvccarpet on Existing floor including bonding material 1.5 mm thick wood colour of approved brand as directed E.I.	Sqm	11.25	
7	Providing and fixing in position (as per 1868 / 1982) Aluminium sliding window of three tracks with rectangular pipe 95 x 38.10 x 0.90 mm at weight 0.637 Kilogram/ Running metre. with window frame bottom track section 92 x 31.75 x 1.30 mm at weight 1.070 Kilogram/Running metre.. Top and side track section 92 x 31.75 x 1.30 mm at weight 0.933 Kilogram/Running metre. As per detailed drawings and as directed by Engineerincharge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass and aluminium mosquito net shutter with stainless steel jail with all required screws and nuts etc, complete.	Sqm	8.64	

Signature and Stamp

**(II) Terms and conditions of supply**

- 1) **The rate should be quoted only after site inspection.**
- 2) The quotation will be accepted on all working days between 11 to 4 P.M. and will be opened on the closing day.
- 3) The quotation should reach this office with samples of material as specified on or before **14.08.2024 at Office of Director, Central Research Station, Dr. PDKV, Akola**
- 4) No labours will be provided by this office.
- 5) This office will not be responsible if any accident happen during the renovation work.
- 6) The rates quoted will have to be inclusive of all taxes with delivery at the Central Store, Central Research Unit, Dr. PDKV, Akola excluding GST.
- 7) The rates quoted will have to be accepted for a period of 1 year from the date fixed for opening the quotation.
- 8) The material will have to be supplied as per specifications within ten days from the date of acceptance of quotation.
- 9) In the event of failure of supply of material within the period the undersigned will be authorized to cancel the order of supply.
- 10) While working, if there is damage to univ. property, the responsibility should be held on contractor.
- 11) The right to accept whole or part of the quotation or reject is reserved with undersigned without assigning reason thereof..

  
 Director,  
 Central Research Station,  
 Dr. PDKV, Akola