



**DIRECTORATE OF EXTENSION EDUCATION
DR. PANJABRAO DESHMUKH KRISHI VIDYAPEETH**

KRISHINAGAR P.O., AKOLA - 444 104 (Maharashtra)

Phone: (0724) 2258174

E-Mail : director_extn@pdkv.ac.in

No. DEE/ATIC/Hall Elect. 267/2022

Date 9/11/2022

Quotation Notice

To,

Subject: - Quotations for providing electrical installation of Conference hall at ATIC....

Sir,

Please arrange to send quotations for providing electrical installation of Conference/ training hall at Agricultural Technology Information Centre, Akola under the Directorate of Extension Education, Dr. PDKV, Akola with particulars and conditions of supply as mentioned below:

S. N.	CSR. No.	Item	Quantity Required	Unit
1	1.2.11	Supplying and erecting PVC trunking (PVC casing-ncapping) of size 32 mm with accessories on wall /ceiling as per specification No: WG-MA/CON.	60	m
2	1.3.1	Supplying & erecting mains with 2x1.5 sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/ inside pole /Bus bars or any otherplaces as per specification No: WGMA/BW	65	m
3	1.3.1N	Supplying & erecting mains with 1x1.5 sq.mm F.R copper PVC insulated wire laid in provided conduit/trunking/ inside pole/Bus bars or any otherplaces as per specification No: WGMA/BW	60	m
4	1.3.5	Supplying & erecting mains with 2x4 sq.mm F.R copperPVC insulated wire laid in provided conduit / trunking /inside pole/Bus bars or any other places. as per specification No: WGMA/BW	40	m
5	1.3.3N	Supplying & erecting mains with 1x2.5 sq.mm F.R copper PVC insulated wire laid in provided conduit / trunking /inside pole / Bus bars or any other places. as per specification No: WGMA/ BW	30	m
6	1.8.1	Supplying and erecting ISI mark modular type switch 6A / 10A duly erected on provided plate and box with wiring connections complete..	3	each
7	1.8.2	Supplying and erecting ISI mark modular type switch 16A duly erected on provided plate and box with wiring connections complete.	3	each
8	1.8.10	Supplying and erecting ISI mark modular type 3 pin 6A multi sockets with safety shutter, duly erected on provided plate and box with wiring connections complete.	3	each
9	1.8.11	Supplying and erecting ISI mark modular type 3 pin 6 /16A multi socket with safety shutter, duly erected on provided plate and box with wiring connections complete.	3	each
10	1.8.23	Supplying and erecting ISI mark modular type (two module) electronic step regulator for fan, duly erectedon provided plate and box with wiring connections complete. Note: Add Rs 57/- for additional two module box with double mounting plate if required.	7	each
11	1.8.30	Supplying and erecting PVC Surface modular switch box with double mounting plate for 6 modules duly erected.	3	each



DIRECTORATE OF EXTENSION EDUCATION
DR. PANJABRAO DESHMUKH KRISHI VIDYAPEETH

KRISHINAGAR P.O., AKOLA - 444 104 (Maharashtra)

Phone: (0724) 2258174

E-Mail : director_extn@pdkv.ac.in

12	1.8.32	Supplying and erecting PVC Surface modular switch box with double mounting plate for 12 modules duly erected.	2	each
13	1.9.13	Wiring for plug on board with Switch socket, copper wiring and earthing as per specification No: WG- PW/SW	3	pt
14	1.9.16	Point wiring in PVC trunking (casing-capping) with 1.5 sq.mm (2+1E) FR grade copper wire, flush type switch, earthing and required accessories as per specification No: WG-W/SW	20	pt
15	1.15.1	Dismantling the existing light, fan, bell, clock, independent plug point, wiring including circuit mains of all types along with accessories etc. complete as per specification No: WG-DM/PW	20	pt
16	2.1.23	Supplying & erecting LED 20W tube light fitting (4 feet) with aluminium housing, heat sink, integrated HF electronic driver complete.	8	each
17	2.12.4	Providing and erecting bracket fan 400 mm. sweep A.C. 230 volts 50 cycles 1350 R.P.M. Oscillating type, plastic or metal blades chrome plated guard with regulator and moisture proof treatment to winding and with 'E' class insulation.	2	each
18	2.12.21	Supplying and erecting five star rated energy saving Ceiling fan 230 V A.C. 50 cycles 1200 mm complete erected in position as per specification no. FG-FN/CF	5	each
19	5.3.2	Supplying, erecting & marking SPMCB 6A to 32A, C- series (for motor/power) in provided distribution board as per specification no. SW-SWR/MCB	6	each
20	5.3.3	Supplying, erecting & marking SPMCB 6A to 32A, B- series (for lighting) in provided distribution board as per specification no. SWSWR/ MCB	6	each
21	5.3.9	Supplying, erecting & marking DPMCB 40A to 63A, B series (for lighting) in provided distribution board as per specification no. SW-SWR/MCB	1	each
22	5.3.24	Supplying erecting and marking four pole isolators only switch version of miniature circuit breakers of 40A in provided distribution board complete.	1	each
23	5.4.11	Supplying & erecting triple pole and neutral distribution board (TPNDB) with door surface/ flush mounted SP / TP MCBs of 8 ways, on iron/ GI frame (vertical busbar type) as per specification no. SW-SWR/MCBDB	1	each
24	5.1.3	Supplying and erecting double pole metal clad switch with HC type fuse and neutral link 240V, 32A on iron / GI frame as per specification no. SW-SWR/MDP.	1	each
25	5.4.20	Supplying, erecting original 1.25 mm CRCA sheet metal enclosures with 20A. 2 pin & earth socket and 20 A. 3 pin plug top with 20A/30A single pole MCB complete erected on angle iron/GI frame.	2	each
26	7.1.30	Supplying, erecting & terminating XLPE armoured cable 4 core 25 sq. mm. aluminium conductor with continuous 5.48 sq. mm. (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe as per specification no. CB-LT/AL	60	m
27	9.1.3	Providing pipe type earthing with 40mm. dia. G.I. pipe or 20 mm dia. G.I. Rod complete with all materials as per specification no. EA-EP	1	each

TERMS AND CONDITIONS OF SUPPLY

1. The quotations should be in favour of **Director of Extension Education, Dr. PDKV, Akola** mentioning Quotation for providing electrical installation of **Conference hall at ATIC.**




DIRECTORATE OF EXTENSION EDUCATION
DR. PANJABRAO DESHMUKH KRISHI VIDYAPEETH

KRISHINAGAR P.O., AKOLA - 444 104 (Maharashtra)

Phone: (0724) 2258174

E-Mail : director_extn@pdkv.ac.in

2. Payment will be released after receiving item or completion and testing of the work as per the specifications mentioned in quotation notice in good condition and quality.
3. Please quote the rate of each item separately **inclusive of GST charges.**
4. **Last date of acceptance of quotation 22/11/2022 up to 17.00 hrs.**
5. The rates quoted will have to be accepted for a period of **6 months** from the date of fixed for opening of the quotation.
6. In the event of failure to complete order within the specific period, the undersigned will be authorized to cancel the order for supply/work.


Director of Extension Education
Dr. PDKV, Akola