Appendix – II (Envelope No.2)

Schedule for Item wise rates to be filled by Contractor

Name of Work: Providing temporary arrangement of mandap, stall, lighting and electrification & other services for Organization of **"AGROTECH-2026"**

Sr. No.	Particulars of work	Qty. more or less	Unit	Per Unit Cost INR	Total cost INR
Item No. 1 a)	**Seminar Dome** : Providing and erecting temporary type waterproof arch type portal frame steel structure with false ceiling & walls of white cloth neat and clean & having minimum clear width of 85 feet & centre height 32 feet & length 105 feet and having seating capacity of 1500 person on fiber chairs, 200 VIP's on two seater sofa sets, including chairs, sofa sets, security 'D' arrangement with baricating as per approved plan, including providing and laying synthetic carpet, electrical arrangement of 70 ceiling fans, 70 tube lights, computerized flex name board of appropriate size at the entrance of hall including separate arrangement of entrance, exit, connected mandap of decorative cloth between stage & seminar hall & fire extinguisher 10 Nos. etc complete. For Facilitation of seating arrangement, preparation of sufficient number of coloured flexes board for fixing inside wall of the dome. (As directed by Director of Extension Education) **Size :- 85 ft. x 105 ft.** (To be provided on gratis to university)	8925 Sqft.	Sqft.		
Item No. 1 b)	**Dais/Stage**: Providing decoration to existing pavilion dais, stage 85 ft. x 25 ft. & height of 15 ft. with decorated cloth for walls, ceiling, jute carpet neat & clean with arrangement of 25 seating capacity with best quality VIP chairs, sofa, teapoy-10 Nos. air cooler symphony - 4 Nos., podium-2 Nos. sound system with cordless mike, recording arrangement VIP toilet near stage, back drop of velvet cloth of approved shade, banner or flex board, samai with stand etc. complete. (As directed by Director of Extension Education) **Stage size – 85 ft. x 25 ft.** (On gratis to university)	2125 Sqft.	Sqft.		
Item No. 2 a)	**Exhibition Dome No. 1** : Providing and erecting temporary type waterproof arch type portal frame steel structure with false ceiling & walls of white cloth neat and clean having minimum size 80 ft x 200 ft & centre height 32 fts, as per approved drawing & **width of passage between two rows of stalls is 20 ft** Flooring of synthetic carpet. **Front side of Dome with 15 ft. should be covered by white decorated cloth/zalar with flooring of green matting.** Dome includes inside arrangement of **exhibition stall size (12 ft x 10 ft) 29 nos., stall size (10 ft x 10 ft) 37 nos., & 2 mega stalls of size 30 ft x 10 ft**, Stall should be in extruded aluminum type with laminated panels fasci in vinyl letters, each stall have to be provided three tables with white cloths, three chairs, three spot lights, two plug points, one waste paper basket & 30 steel hooks for hanging exhibits. Electrical Arrangement in dome, 70 ceiling fans 70 No. tube lights etc. & 10 fire extinguishers, however if needed extra chairs & tables will have to be provided, as per requirement etc. complete. (As directed by Director of Extension Education)				
	Dome size : 80 ft. x 200 ft.	**16000 Sqft.**	**Sqft.**		
	Stalls size: 12 ft x 10 ft. (To be provided on gratis to university)	29 Nos.	No		
	Stalls size: 10 ft x 10 ft. (To be provided on gratis to university)	37 Nos.	No		
	Mega stall Size: 30 ft. x 10 ft. (To be provided on gratis to university)	02 Nos.	No		

Item no. 2 b)	**Exhibition Dome No. 2 :** Providing and erecting temporary type waterproof arch type portal frame steel structure with false ceiling & walls of white cloth neat and clean having minimum **size 80 ft x 150 ft & centre height 32 fts,** as per approved drawing & **width of passage between two rows of stalls is 20 ft**. Flooring of synthetic carpet. **Front side of Dome with 15 ft. should be covered by white decorated cloth/zalar with flooring of green matting.** Dome includes inside arrangement of exhibition stall size 10 ft x 10 ft 50 nos., the stall should be in extruded aluminum type with laminated panels fasci in vinyl letters, each stall have to be provided three tables with white cloths, three chairs, three spot lights, two plug points, one waste paper basket & 30 steel hooks for hanging exhibits. **(stalls to be booked and marketed by the contractor.)** Electrical Arrangement in dome, 60 ceiling fans 60 No. tube lights etc. & 10 fire extinguishers, however if needed extra chairs & tables will have to be provided, as per requirement etc. complete. (As directed by Director of Extension Education)		
	Dome size : 80 ft. x 150 ft.	12000 Sqft.	Sqft.
	Stalls size : 10 ft x 10 ft.	50 Nos.	No
Item no. 2 c)	**Exhibition Dome No. 3** : Providing and erecting temporary type waterproof arch type portal frame steel structure with false ceiling & walls of white cloth neat and clean having minimum **size 80 ft x 150** ft & centre height 32 ft, as per approved drawing & width of passage between two rows of stalls is 20 ft. Flooring of synthetic carpet. **Front side of Dome with 15 ft. should be covered by white decorated cloth/zalar with flooring of green matting.** Dome includes inside arrangement of exhibition stall **size 10 ft x 10 ft 50 nos.,** the stall should be in extruded aluminum type with laminated panels fasci in vinyl letters, each stall have to be provided three tables with white cloths, three chairs, three spot lights, two plug points, one waste paper basket & 30 steel hooks for hanging exhibits. **(Stalls to be booked and marketed by the contractor.)** Electrical Arrangement in dome, 60 ceiling fans 70 No. tube lights etc. & 10 fire extinguishers, however if needed extra chairs & tables will have to be provided, as per requirement etc. complete. (As directed by Director of Extension Education)		
	Dome size : 80 ft. x 150 ft.	12000 Sqft.	Sqft.
	Stalls size : 10 ft. x 10 ft.	50 Nos.	No
Item no. 2 d)	**Exhibition Dome No. 4**: Providing and erecting temporary type waterproof arch type portal frame steel structure with false ceiling & walls of white cloth neat and clean having minimum size 80 ft x 200 ft & centre height 32 fts, as per approved drawing & **width of passage between two rows of stalls is 20 ft** Flooring of synthetic carpet. **Front side of Dome with 15 ft. should be covered by white decorated cloth/zalar with flooring of green matting.** Dome includes inside arrangement of **exhibition stall size 10 ft x 10 ft 80 nos.,** the stall should be in extruded aluminum type with laminated panels fasci in vinyl letters, each stall have to be provided three tables with white cloths, three chairs, three spot lights, two plug points, one waste paper basket & 30 steel hooks for hanging exhibits. Electrical Arrangement in dome, 70 ceiling fans 70 No. tube lights etc. & 10 fire extinguishers, however if needed extra chairs & tables will have to be provided, as per requirement etc. complete. (As directed by Director of Extension Education)		
	Dome Size (80 ft X200 ft)	16000 Sqft.	Sqft.
	Stalls size : 10 ft. x 10 ft. (On gratis to university)	80 Nos.	No

Item no. 2 e)	**Exhibition Dome No. 5**: **(Floriculture)** Providing and erecting temporary type waterproof arch type portal frame steel structure with false ceiling & walls of white cloth neat and clean having minimum size 70 ft x 150 ft & centre height 32 fts, as per approved drawing & **width of passage between two rows of stalls is 20 ft** Flooring of synthetic carpet. **Front side of Dome with 15 ft. should be covered by white decorated cloth/zalar with flooring of green matting.** Dome includes inside arrangement of 10 stalls **size 10 ft x 10 ft** as per requirement**,** the stall should be in extruded aluminum type with laminated panels fasci in vinyl letters, each stall have to be provided three tables with white cloths, three chairs, three spot lights, two plug points, one waste paper basket & 30 steel hooks for hanging exhibits. Electrical Arrangement in dome, 60 ceiling fans 60 No. tube lights etc. & 10 fire extinguishers, however if needed extra chairs & tables will have to be provided, as per requirement etc. complete. (As directed by Director of Extension Education)		
	Dome Size (70 ft X 150 ft)	10500 Sqft.	Sqft.
	Stalls size : 10 ft. x 10 ft. (On gratis to university)	10 Nos.	No
Item No. 3	Providing & erecting decorated cloths mandap size 35 ft x 70 ft for **seminar.** The stalls frame should be made from 40 mm dia m.s. pipe or wooden ballies & ceiling & walls covered by decorated or white cloth, green carpet for flooring, Dias 20X15 ft, 200 Chairs, 03 teapoy, VIP chair/soafa for 10 persons air cooler, fan 10, tubelight 15 aongwith decorative entrance gate, backdrop 10 x 10 with cordless mike, podium, sound system etc.computerised name board of flex at entrance, **(ON GRATIS TO UNIVERSITY)**	2450 sqft	Sq ft
Item No. 4 a)	Providing & erecting decorated cloths mandap for **self-help group stalls & for innovative farmers stalls.** The stalls frame should be made from 40 mm dia m.s. pipe or wooden ballies & ceiling & walls covered by decorated or white cloth, synthetic carpet for flooring, two tables with white cloths, **four** chairs in each stall. Ceiling height of stall is 12 feet, computerised name board of flex at entrance of stalls, sufficient lighting arrangement including three tube light & two plug points, one dustbin in each stall. **(ON GRATIS TO UNIVERSITY)**		
	For innovative farmers/Self Help group stall size: 10 ft. x 10 ft. (30 Nos). Front side passage 5 ft. for each stall. Covered with white cloth & fixed in bamboo ballies with green matting floor between two rows of stall (15x150 feet)	3000 Sqft. 2250 Sqft.	Sqft.
Item No. 4 b)	Providing & erecting decorated cloths mandap **for self-help group food & snacks stalls.** The stalls frame should be made from 40 mm dia m.s. pipe or wooden ballies & ceiling & walls covered by decorated or white cloth, synthetic carpet for flooring, cover all passage area ceiling by cloth and with green matting four tables with white cloths and six chairs in each stall. Ceiling height of stall is 12 feet, computerised name board of flex at the entrance of stalls, sufficient lighting arrangement including three tube light & two plug points, one dustbin in each stall. **(ON GRATIS TO THE UNIVERSITY)**		
	Self Help group Food & Snacks stalls size: 20 ft. x 20 ft. (30 Nos) Front side passage 25 ft. for each stall. Covered with white cloth & fixed in bamboo ballies with green matting floor between two rows of stall. (25x25 feet) x 30 stalls	12000 Sqft 15000 Sqft.	Sqft.
Item No. 5 a)	Providing & erecting decorated cloth mandap for **tractors stalls.** The stalls frame should be made from 40 mm dia m.s. pipe or wooden ballies & ceiling & walls covered by decorated or white cloth, synthetic carpet for flooring, two tables with white cloths ,and five chairs, in each stall, ceiling height of stall is 12 feet,		

	computerized name board of flex at the entrance of stalls, sufficient lighting arrangement including six tube lights & two plug points, one dustbin in each stall. (ON GRATIS TO UNIVERSITY)		
	Tractor stall size:15 ft.x15 ft. (15 No) (to be marketed by contractor)	3375 sqft.	Sqft.
	Agril. Engg. Demo stalls size : 15 ft. x 15 ft. (15 Nos) (ON GRATIS TO THE UNIVERSITY)	3375 sqft	Sqft.
Item No. 5 b)	Providing & erecting decorated cloth mandap for **machinaries/ implements and SHGs.** The stalls frame should be made from 40 mm dia m.s. pipe or wooden ballies & ceiling & walls covered by decorated or white cloth, synthetic carpet for flooring, two tables with white cloths ,and five chairs, in each stall, ceiling height of stall is 12 feet, computerized name board of flex at the entrance of stalls, sufficient lighting arrangement including six tube lights & two plug points, one dustbin in each stall. (ON GRATIS TO UNIVERSITY)		
	20X40 ft (1 stalls)	800 sqft	
	15X15 ft (10 stalls)	2250 sqft	
	20X20 ft (7 stalls)	2800 sqft	
Item No. 6	Providing & erecting decorated cloth mandap for Cattle stalls. The stalls frame should be made from 40 mm dia m.s. pipe or wooden ballies & ceiling & walls covered by decorated or white cloth, with covering of frontside of each stall in night. Front side passage 5 ft. for each stall Covered with white cloth & fixed in bamboo ballies with green matting floor between two rows of stall (5x50 ft x 25=750), synthetic carpet for flooring, two tables with white cloths ,and three chairs, in each stall, ceiling height of stall is 12 feet, computerised name board of flex at the entrance of stalls, sufficient lighting arrangement including three tube lights & two plug points, one dustbin in each stall. Decorative entrance gate 20x15 ft., Water Tub for cattle drinking, Complete barricading for 25 stalls, Still hook for tiding of animals in the stall (ON GRATIS TO THE UNIVERSITY) **Cattle Stalls size : 10 ft. x 10 ft. (25 Nos)**	2500 sqft.	Sqft.
Item No. 7	Providing & erecting decorated cloth mandap for **Registration counter.** The stalls frame should be made from 40 mm dia m.s. pipe or wooden ballies & ceiling & walls covered by decorated or white cloth, synthetic carpet for flooring, 15 tables with white cloths, and 40 chairs, in each stall, ceiling height of stall is 12 feet, computerized name board of flex at the entrance of stalls, sufficient lighting arrangement including six tube lights & two plug points, one dustbin in each stall. **Registration counter size: 30 ft. x 20 ft. (2 Nos)**	1200 Sqft.	Sqft.
Item No. 8	Providing & erecting decorated cloth mandap for **control room.** The stalls frame should be made from 40 mm dia m.s. pipe or wooden ballies, ceiling & walls covered by decorated or white cloth, synthetic carpet for flooring, five tables with white cloths ,and five chairs, in each stall, ceiling height of stall is 12 feet, computerized name board of flex at the entrance of stalls, sufficient lighting arrangement including six tube lights & two plug points, one dustbin in each stall. One Big TV panel in control room with operator	3200 Sqft.	Sqft.
	Control Room size : 20 ft. x 20 ft. (1 Nos) (On gratis to university)	400 Sqft.	Sqft.
	Waiting Room : 20 ft.x 20 ft. (2 Nos) (On gratis to university) 10 no. two seater VIP sofa, 03 teapoy, 03 air cooler, complete red carpet	800 Sqft.	Sqft.
Item No. 9	Providing partition wall of **Decorative Kanat** in front of Exhibition dome for passage alongwoth floriculture dome. Kanat made from new a decorative cloth of Height 12 feet fitted on wooden balli/ bambu etc. **a) Kanat**	6900 feet	Rft.

Item No. 10	Providing & erecting **decorative entrance gate** at the entrance of exhibition & separation of entrance gate for men & women, including flag posts with coloured flags and red colour carpet on pathway of main stage 10 no of halogen Lights on road side. Along with series lighting at appropriate places.	3 Nos.	Nos
Item No. 11	Providing **signage board** displaying general signage will have to be fixed at various places for information etc (As directed by Director of Extension Education) Size : 1 ft. x 2 ft.	10 Nos.	No.
Item No. 12	Providing **hydrogen gas balloon** of 25 ft. diameter endorsing logo & name of Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola at the site of Exhibition. All necessary arrangements viz. balloon, hydrogen gas cylinder for filling of the balloon and erection of the balloon in air will have to be arranged by the Mandap contractor. The balloon should be kept in air for four days i.e. 26/12/2026 to 29/12/2026.	1 No.	No.
Item No. 13	Providing **RO Drinking water arrangement on exhibition ground 400 water cans/spots/day (Total 5 spots)** and frequently filled with RO drinking water & glasses, alongwith a two persons for distribution of water at each spots to visitor's on exhibition ground, including drainage arrangement. **Also give two water cans/day to each stalls separately.**	1 job	No.
Item No. 14	Providing **parking arrangement** for two and four wheelers with markings, Barricades of wooden ballies height 1 mtr. and CCTV camera and security guards. Sufficient number of parking separation boards be kept ready (As per the direction of officer in-charge.)	1500 Ft.	Rft.
Item No. 15	Providing **generator** sets for 24 hour power supply with fuel & operator during the work & during the period of exhibition. Set should be proper in working condition noiseless, smokeless.		
	a) Generator set with mobile van 125 KVA	3 Nos.	No
	b) Generator set 40 KVA	2 Nos.	No.
Item No. 16	Providing 500 watt P. A. / **sound system with cordless mike**, speaker and amplifiers. Recording system at the stage Registration counter control room etc.	2 Nos.	No.
Item No. 17	Providing **firefighting** arrangements with fire brigade van. Sufficient no. of Fire extinguishers with operator or as per the statutory norms Fire bucket filled with sand as per requirement etc. complete.	1 Job	Job
Item No. 18	Providing Security Services **(MESMA/Any other reputed agency)** with **40 Security guards (Male & Female)** in uniforms with cap, logo, batten, whistle form a reputed security firm in **morning** & 10 guards during **night** hour for 3 day etc complete	1 Job.	Job
Item No. 19	Providing **house keeping** with 20 sweepers with uniform & labours for keeping campus cleaning, carting of wastage material, sweepers for keeping the toilets neat & clean etc. including sanitary material etc. complete. Cleaning of exhibition site at regular interval will be required during the period of exhibition. Garbage has to be lifted (Approx. 2 trip/day through vehicle) from ground on daily basis.	1 Job.	Job
Item No. 20	Providing **visitors counting** machine of five counting sets at the entrance No. 1 & 2 at both places & counting the visitors at the end of every day and submission data of total visitors in three days etc.	1Job	Job
Item No. 21	Providing **Landscaping** at selected five spots in the guidance of Horticulturist. (size of each spot 20 ft x 10 ft.)	1 Job	Job
Item No 22	Providing first aid facility as well as **ambulance.**	1 Job	Job
Item No. 23	Providing services of following types, Interior **Decorator, banner** makers & any other related service. a) Hostess cum announcer (3 Nos.)	1 Job	Job

	b) Technology boards (6 Nos.) c) Banner makers (backdrops of main Dias all the three days for various event)		
Item No. 24	Providing sufficient no. of **flowers bouquets for VVIP 15 Big Size flowers bouquets, for VIP 20 Medium size flowers bouquets for each day** on inaugural function & concluding days etc. and other day 20 no. regular **flowers bouquets**.	1 Job	Job
Item No. 25	Providing facility & service for telecom courier, banks, travel booking etc. **(Special counter with concern booking person/ agencies)**	1 Job	Job
Item No. 26	Providing and supplying following various items on exhibition ground as per requirement and directions.		
1	Synthetic Green carpet for passages	1,25,000 Sqft.	Sqft.
2	Jute carpet / Red non woven carpet	7200 sqft.	Sqft.
3	Table with white cloth	300 Nos.	No.
4	Chair	300 Nos.	No.
5	Tube light	50 Nos.	No.
6	Fan	20 Nos.	No.
7	Desert cooler	5 Nos.	No.
8	Tea Poy	5 Nos.	No.
9	Fire extinguisher	20 Nos.	No.
10	Plug point	20 Nos.	No.
11	Kanat 6 ft. ht.	500 Sqft.	Sqft.
12	Baricating 4 ft. ht.	1000 Rft.	Rft.
13	Soffa set	5 Nos.	No.
14	Lighting series (LED)	2000 Mtr.	Mtr
15	Street Drama stage with 2 ft height	01	No.
16	LED Wall on Stage and Front of Seminar dome (8x12 ft)	02	No.
17	Selfie point	02	No.
18	E vehicle	02	No.
19	Dust bins–decorative and covered with flap having capacity 15 lit	50	No.
20	CCTV Camera with PTZ Camera System Installation of Fifteen CCTV camera set and Central Management with system	15	No.
Item No. 27	Providing and erecting requisite number of **lavatories/urinals for gents and ladies** separately, including VIP lavatory near main dias and near waiting room of dignitaries Ready to use W.C. toilet blocks.		
	Lavatory block Gents	5 Nos.	No.
	Lavatory block Ladies	5 Nos.	No.
	Ready to use Mobile toilet block (w.c.) Gents	5 Nos.	No.
	Ready to use Mobile toilet block (w.c.) Ladies	5 Nos.	No.
Item No. 28	Providing **safety covering with Tin Sheets** of height 10 ft. or any other item to cover entire area of exhibition or spots ground.	1500 Rft.	Rft.
Item No. 29	Providing temporary highmast type **lighting arrangement** at the centre of exhibition ground etc complete. **Height - 30 feet - No of lights - 32 Nos.**	10 Nos.	No
Item No. 30	**Publicity**: Paper advertisements of event in colour in local (atleast 5 newspaper) and state level newspapers (atleast 10 newspapers viz. Lokmat, Sakal, Deshonnati, Dainik Bhaskar, Tarun Bharat, Loksatta, Hitwad, Maharashtra Times, etc.) in size of 5x4 inches and as per Govt. rates. Published AGROTECH news in various newspapers should be produce/submit to this office for final payment. Big hoarding for Akola city (5 NO.), 10,000 posters (1.5 x 3 ft.), 3000 A4 size coloured letters and information brochures for distribution in Vidarbha and outside Vidarbha) have to be done by mandap contractor. The University will do its own publicity of exhibition for larger participation of farmers. Event manager should supply sufficient number of posters, letters and brochure to the University.		

Signature & Stamp of
Contractor with
Full address & Telephone No. & Mobile No.