



**DIRECTORATE OF EXTENSION EDUCATION
DR. PANJABRAO DESHMUKH KRISHI VIDYAPEETH**

KRISHINAGAR P.O., AKOLA - 444 104 (Maharashtra)

Phone: (0724) 2258174

E-Mail : director_extn@pdkv.ac.in

No. DEE/ATIC/Plith/ 1110 /2023

Date: 23/08/2023

Quotation Notice

To,

Subject: - Quotations for Construction of Concrete platform for irrigation display unit at ATIC

Sir,

Please arrange to send **Quotations for Construction of Concrete platform for irrigation display unit at ATIC** under the Directorate of Extension Education, Dr. PDKV, Akola with particulars and conditions of supply/work as mentioned below:

Sr. No.	Particulars	Approximate Quantity	Cost per No. (Rs.)
01	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area & stacking and spreading as directed. Dewatwering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift up to 1.5 m) by manual means [CSR item No. 21.02]	6.91 Cum	
02	Providing and laying cast in situ/Ready Mix cement concrete in M-10 of trap/granite/quartzite/gneises metal for foundation and bedding including bailing out water, from work, laying/pumping compacting, roughening them if special finish is to be provided, finishing if required and curing complete. with fully automatic micro processor based PLC with SCADA enabled reversible drum type mixer/concrete batch mix plant etc. complete With natural sand/VSQuality Artificial sand [CSR Item No. 24.01]	1.15 Cum	
03	Providing second class burnt brick masonry with conventional/IS type brick in cement mortar 1.6 in foundation and plinth of inner walls/in plinth external walls including bailing out water manually, striking joints on unexposed faces, raking out joints on exposed face and watering etc. Complete [CSR Item No. 27.01]	6.01 Cum	
04	Filling in plinth and floors with contractors material/brought from outside and approved by engineer incharge in layers of 15 cm to 20 cm including watering and compacting etc. complete Spec. No. Bd.A11/page N. 263 [CSR Item No. 21.37]	4.30 Cum	
05	Providing soling using 80 mm size trap metal in 15 cm layer including filling voids with crushed sand /grit, ramming, watering etc. complete. [CSR Item No. 21.40]	2.15 Cum	

Conti---2



**DIRECTORATE OF EXTENSION EDUCATION
DR. PANJABRAO DESHMUKH KRISHI VIDYAPEETH**

KRISHINAGAR P.O., AKOLA - 444 104 (Maharashtra)

Phone: (0724) 2258174


E-Mail : director_extn@pdkv.ac.in

--2--

06	Providing and laying Cast in situ/ready mix cement concrete in M-15 of trap/granite/quartzs metal for bed blocks, foundation blocks and such other items including bailing out water, plywood/steel/formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finshing uneven and honeycombed surface and curing etc. complete. The cement mortar 1:3 plaster is considered for rendering uneven and honeycombed surface aonly. Newly lid concrete shall be covered by gunny bag, plastic etc. . with fully automatic micro processor based PLC with SCADA enabled reversible drum type mixer/concrete batch mix plant etc. complete With natural san/VSIquality Artificial sand [CSR Item No. 24.08]	1.44 Cum	
07	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using water proofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough toreceive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curring for fourteen days scaffolding etc Complete [CSR Item No. 32.11]	10.08 Cum	
08	Providing and applying two coats of exterior weather shield paint of approved manufacturer and of approved colour to the plastered surfaces including cleaning , preparing the plaster surface, applying primer coat, scaffolding if necessary nd watering the surface for two days etc complete work [CSR Item No. 35.26]	10.08 Cum	

TERMS AND CONDITIONS OF SUPPLY

1. The quotations should be in favour of **Director of Extension Education, Dr. PDKV, Akola** mentioning **Quotation Quotations for Construction of Concrete platform for irrigation display unit at ATIC.**
2. Payment will be released after receiving item or completion and testing of the work as per the specifications mentioned in quotation notice in good condition and quality.
3. Please quote the rate of each item separately **inclusive of GST charges.**
4. **Last date of acceptance of quotation 31/08/2023 up to 17.00 hrs.**
5. The rates quoted will have to be accepted for a period of **6 months** from the date of fixed for opening of the quotation.
6. In the event of failure to complete order within the specific period, the undersigned will be authorized to cancel the order for supply/work.


Director of Extension Education
Dr. PDKV, Akola