

AICRP for Dryland Agriculture
Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola

No. AICRPDA/ 416 /2021

Date: 12/02/2021

QUOTATION NOTICE

To,

Subject: Quotation notice for Excavation of Farm pond of size 20X20X3 m (side slope 1.5:1) at Village Warkhed Tal. Barshitakli Dist Akola under AICRP for Dryland Agriculture, Dr. PDKV, Akola.

Dear Sir,

Under AICRP for Dryland Agriculture, Dr. PDKV, Akola, the excavation of the Farm pond of size 20X20X3m (side slope 1.5:1) at village Warkhed Tal. Barshitakli Dist. Akola has to be undertaken. You are therefore requested to offer your most comparative rates towards this work. Rates should be quoted including all taxes. Furnish quotations under sealed cover so as to reach this office on or before **22.02.2021 upto 5:00 p.m.**


Name of Work: Excavation of Farm pond of size 20X20X3 m (side slope 1.5:1) at village Warkhed Tal. Barshitakli Dist. Akola. Capacity: 741 cum.

SN	Particulars	Unit	Rate
1.	Excavation in all kinds of soil including boulders up to 0.6 m diameter (0.113 cum) for canal seating of embankment, filter drains/catch water drains etc. and placing the excavated stuff neatly in dump area or for formation of service road/embankment including cost of all materials, machinery, labour, dressing bed, and sides to required level and profile etc complete with lead up to 15 m and all lifts as directed.	cum	
2.	Excavation in hard murum including boulders up to 0.6 m diameter (0.113 cum) for canal seating of embankment, filter drains/catch water drains etc. and placing the excavated stuff neatly in dump area or for formation of service road/embankment including cost of all materials, machinery, labour, dressing bed, and sides to required level and profile etc complete with lead up to 15 m and all lifts as directed.	cum	
3.	Excavation in soft rock without blasting including boulders up to 0.6 m diameter (0.113 cum) for canal seating of embankment, filter drains/catch water drains etc. and placing the excavated stuff neatly in dump area or for formation of service road/embankment including cost of all materials, machinery, labour, dressing bed, and sides to required level and profile etc complete with lead up to 15 m and all lifts as directed.	cum	
4.	Excavation in hard rock of all toughness by blasting including boulders up to 0.6 m diameter (0.113 cum) minimizing damage to side slopes of excavation in water prism area by adopting any one or combination of line drilling/pre splitting /smooth blasting techniques and placing the excavated rock neatly in approved dump area cost of all materials, machinery, labour, levelling etc complete with lead up to 15 m and all lifts as directed.	cum	

5.	Inlet for water inflow with 600 mm NP-2/NP-3/ class pipe including jointing of pipe & stone apron 300 mm thick 1 sq. m at each end etc. Complete.	m	
6.	Outlet for water outflow with 600 mm NP-2/NP-3/ class pipe including jointing of pipe & stone apron 300 mm thick 1 sq. m at each end etc. Complete.	m	
7.	Laying of UV stabilized HDPE geo membrane 300/500 micron film as per ISI Standard or an equivalent over the slopes with proper lapping and fixing including proper finishing etc. Complete.	sqm	

Conditions:

1. The quotation should be sent in sealed envelope.
2. On the envelope following should be clearly mentioned in block letters.
Quotation for Excavation of Farm pond of size 20X20X3m at Village Warkhed Tal. Barshitakli Dist. Akola under AICRP for Dryland Agriculture, Dr. PDKV, Akola 2020-21.
3. Extra charges on part of transportation/ labour/fuel, etc. will not be provided.
4. The quotation received after due date will not be accepted.
5. The undersigned reserve the right to accept or reject any or all quotations.
6. The contractor have to submit the Xerox copies of valid license/pan card no./GST/Bank Pass Book account/ Identity card/Insurance etc. alongwith the quotation for undertaking the above mentioned work.
7. The contractor should have the valid R.C. Book/license/pan no./insurance/GST/ etc. of the machineries to be used at the site for undertaking the above mentioned work. This office will not be responsible for any lacuna in the necessary documents or process.
8. The work should be undertaken as per directives of this office personals and the technical specifications should be followed strictly. If proper technicality in work is not observed /followed then the work will be withdrawn.
9. Before commencement of the work the contractor whose rates will be lowest and will fulfill all the required conditions have to give the written undertaking on 100 Rs. Stamp paper towards completion of the work once started. In any case the work should not be left in between. Partial payment will not be done in any circumstances. This office will not be responsible for any such circumstances/payments.
10. The work should be undertaken immediately on farmers field at village Warkhed Tq. Barshitakli dist. Akola or adjacent villages (within 2 days) after receiving the work commencement order from this office.


12/02/2021

Chief Scientist
AICRP for Dryland Agriculture
Dr. PDKV, Akola