



Department of Vegetable Science
Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola

No/HD/VS/Quot/Publish/218 /2024-25

Dated: 18/06/2025

QUOTATION NOTICE

To,

1. Online publication
2. Notice board

Subject: - Supply the quotation for providing and constructing new room between two existing buildings at Department of Vegetable Science, Dr. PDKV, Akola 2024-25


Please arrange to send quotation for providing and constructing new room between two existing buildings at Department of Vegetable Science, Dr. PDKV, Akola as per the particulars and conditions attached separately.

Note : The quotation should reach to this office by dated. 25/06/2025

Head
Dept. Vegetable Science
Dr. P.D.K.V., Akola

CONDITIONS :

1. The quotation should be sent in sealed envelope on the name of undersigned.
2. On the enveloped following should be clearly mentioned in block letters, **Quotations notice for providing and constructing new room between two existing buildings at Department of Vegetable Science, Dr. PDKV, Akola 2024-25, Enquiry letter no. HD/VS/Quot./Publish/218 /2024-25, dated: 18/ 06/2025**
3. Price / rates should be 'exclusive of all GST/CST/VAT taxes and other expenses
4. The **GST/CST/VAT or Professional tax no.** must be mentioned on quotation letter.
5. **Civil contract certificate** must be attached with quotation.
6. **GST certificate, PTA certificate, PAN card and income tax return off last two years** must be attached with quotation.
7. Item available in ready stock and which can be supplied on placing firm order, may only be quoted.
8. The payment of bill can only be made after satisfactory compliance of complete supply/work and hence condition such as full or partial payment in advance, etc, are not acceptable.
9. Details specification, make, models, manufacturer, accessories, required. The quotation for the items for which rates a quoted. The incomplete details/ specification are liable to be rejected.
10. Time period for which the quotation will be valid should be clearly mentioned. Further the validity period should be up to **31st March, 2026.**
11. Quotation received after order date will not be considered.
12. Conditional quotations are liable to be rejected.
13. The undersigned reserves full right to reject any or all quotation without assigning reasons thereof.
14. Authorization letter/ certificate in the support of the authorization dealer of the company may be attached with the quotation.
15. The received sealed envelope quotations will be opened on **26/ 06 /2025 at 10.00 am.** in the chamber of undersigned in presence of staff members.


Head
Dept of Vegetable Science,
Dr. P.D.K.V., Akola



QUOTATION FOR

**NAME OF WORK : PROVIDING AND CONSTRUCTING NEW ROOM
BETWEEN TWO EXISTING BUILDING OF DEPARTMENT OF
VEGETABLE SCIENCE, DR. PDKV., AKOLA**


**Name of Work: Providing and constructing new room between two existing building of
Department of vegetable science, Dr. PDKV., Akola**

"ABSTRACT SHEET"

S.N.	Qty.	Description of Items	Unit
1	Job Work	Dismantling the old septic tank and old GI sheet structure at proposed site Job work	Job Work
2	2.10	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means S.S.R. I. No 21.02	Cum
3	6.30	Excavation for foundation in Hard murum including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5 to 3.0m.) By Mechanical Means S.S.R. I. No 21.08	Cum
4	4.18	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centring, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) S.S.R. I. No 24.10	Cum
5	1.70	Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centring formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) S.S.R. I. No 25.11	Cum
6	0.61	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawing	Cum

		or as directed including steel centring, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade S.S.R. I. No 25.31	
7	1.55	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite/quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centring, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) S.S.R. I. No 25.50	Cum
8	0.20	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. chajja as per detailed design and drawings including steel centring, formwork, cover blocks, laying/pumping, compacting and roughening the surface if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) S.S.R. I. No 26.05	Cum
9	0.34	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. S.S.R. I. No 26.33	MT
10	1.09	Providing fly ash brick masonry with conventional / I.S. type fly ash bricks in C.M. 1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete S.S.R. I. No 27.12	Cum
11	6.81	Providing fly ash brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	Cum

		S.S.R. I. No 27.13	
12	17.64	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete S.S.R. I. No 21.37	Cum
13	6.41	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete S.S.R. I. No 21.40	Cum
14	43.00	Providing and laying hand cut polished Kotah Stone flooring 25mm to 30mm thick and 30cm wide in plain/diamond patten non a bed of 1:6 C.M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete. S.S.R. I. No 33.07	Sqm
15	86.32	Providing and applying Two coats of wall care Putty on plastered surface and Ceiling and Walls to prepare surface even and smooth of approved make, etc complete. S.S.R. I. No 32.34	Sqm


 Head
 Dept. Vegetable Science
 Dr. P.D.K.V., Akola