

## DEPARTMENT OF VEGETABLE SCIENCE Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola

No. HD/VS/Quot./ 276 /2021

Date: 25 / 08 /2021

## **QUOTATION NOTICE**

| Го, |       |  |
|-----|-------|--|
|     | ••••• |  |
|     |       |  |
|     |       |  |

**Subject:** Quotations for providing and laying vitrified tiles for flooring and skirting to the Laboratory of Department of Vegetable Science, Dr. PDKV, Akola....

Please arrange to send sealed quotation for providing and laying vitrified tiles for flooring and skirting to the Laboratory on the conditions mentioned on overleaf.

| Item No. 1 | Removing Shahabad or Tandur stone from floor without bed concrete including stacking the materials as directed with all lead, lifts etc. complete.   |   |  |
|------------|--|---|--|
|            | Room size  | 1x50'.9"x24'.0                              |  |
|            | Area for removing shahabad   | 1218 sq.ft. (Approx.)                       |  |
| Item No. 2 | Providing and casting in situ cement concrete M-75 (1:4:8) of trap/granite/quartize/gneiss metal for bed blocks, foundation blocks   |   |  |
|            | Volume or quantity of concrete (Room)  | 1x50'.9"x24'.0x4"= 401.94 cu.ft.            |  |
|            | Total quantity of concrete   | 401.94 cu.ft. (Approx.)                     |  |
| Item No. 3 | Providing and laying vitrified tiles of approved make and quantity of required size and thickness for flooring is required position laid on bed of CM 1:6 including cement float, filling joint with white/colour cement slurry cleaning curing etc. Complete 600 mm x 600 mm size |   |  |
|            | Area of floor  | 1x50.9x24.0 = 128  sq.ft.                   |  |
|            | Skirting   | 2x50.9 + 2x24.0 = 149.5 RH                  |  |
|            | Height of skirting   | 6"  |  |
|            | Area of skirting   | $149.5 \times 0.5 = 74.75 \text{ sq.ft.}$   |  |
|            | Area   | 1218 sq.ft. + 74.75 sq.ft. = 1292.75 sq.ft. |  |
|            | Waste (4%)   | 52.00 sq.ft.                                |  |
| 4          | Total area   | 1344.75 sq.ft. (Approx.)                    |  |

| Item No. 4   | Providing and laying vitrified/parking tiles required size and thickness for flooring in relational tiles including cement float, filling joint cleaning curing etc. Complete  Size:300 mm x 300 mm | equired position laid on bed of CM                                    |
|--------------|---|---|
| 80 ; 2 \ 2in | Area of floor   | 1x50.9x6.6 = 329.87  sq.ft. Say 330.00 sq.ft. Waste (4%) 13.00 sq.ft. |
|              | Total area  | 343.00 sq.ft. (Approx.)   |

NOTE: -The quotation should be reach to this office by dated 03/09/2021/at 5.00 pm.

Head
Department of Vegetable Science
Dr. PDKV., Akola

## **CONDITIONS:**

- 1. The quotation should be sent in sealed envelope.
- 2. On the left corner of envelope following matter should be clearly mentioned in block letters. 'Quotation for providing and laying vitrified tiles for flooring and skirting to the Laboratory for Laboratory at Farm, Department of Vegetable Science, Dr. PDKV, Akola with reference to this office enquiry letter no. and date, HD/Hort/Quot./ /2021, dated: /08/2021
- 3. Quotation should be send in the name of Head, Department of Vegetable Science, Dr. PDKV, Akola and address for correspondence is as undersigned.
- 4. The CGST, SGST or Professional tax no. must be mentioned in quotation letter.
- 5. The quoted price/rates should be 'all inclusive/exclusive' (i.e. GST & other expenses) as per guidelines of Govt. of India/Maharashtra.
- 6. Whatever GST applicable for the services, it should be mention separately in the final credit bill according to the billing proforma.
- 7. The payment of bill can only be made after satisfactory compliance of complete work/supply of materials and hence condition such as full or partial payment in advance, etc, are not acceptable.
- 8. The quotations with incomplete details/specifications are liable to be rejected.
- 9. The contractor should visit the site before submission of quotation.
- 10. Time period for which the quotation will be valid should be clearly mentioned. Further the validity period should be up to 31 March 2022.
- 11. Warranty period should be clearly mentioned.
- 12. Quotation received after last date will not be considered.
- 13. Conditional quotations are liable to be rejected.
- 14. The contractor should submit registration certificate of contractor-ship issued by competent authority along with quotation.
- 15. The undersigned reserves full right to reject any or all quotation without assigning reasons thereof.
- 16. Authorization letter/ certificate in the support of the authorization dealer of the company may be attached with the quotation.
- 17. The received sealed envelope quotations will be opened on 03/09/2021 at 5.30 pm. in the chamber of undersigned in presence of staff members.

Department of Vegetable Science Dr. PDKV., Akola