DEPARTMENT OF VEGETABLE SCIENCE
Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola

No. HD/VS/Quot./ 280 /2021   Date: 25/ 8 /2021

QUOTATION NOTICE

To,

....

....

..

Subject: Quotations for providing and constructing brick work, coping and plastering work of farm store at Department of Vegetable Science, Dr. PDKV, Akola....

Please arrange to send sealed quotation for providing and constructing brick work, coping and plastering work of farm store on the conditions mentioned on overleaf.

Item No.-1	Providing 2nd class burnt brick masonry with conventional/I.S. type brick in cement mortar 1:6 foundation and plinth of inner walls/in plinth of external walls including bailing outer water, striking joints on unexposed faces, racking out joints on exposed faces and watering complete (9" thick wall)	
	Shed long wall	2x36'.6"x3'.0 = 219.0 sq.ft.
	Shed short wall	2x3x11'.9"x3'.0 = 211.50sq.ft.
	Varanda wall	1x3.0x3.0 = 9.0 sq.ft. 1x10.0x3.0 = 30.0 sq.ft. 1x5.0x3.0 = 15.0 sq.ft.
	Steps	1x5.0x2.0 = 10.0 sq.ft. 1x5.0x1.0 = 5.0 sq.ft.
	Deduction	1x7.0x3.0 = 21.0 sq.ft.
	shutter	1x10.0x3.0 = 30.0 sq.ft.
	Net quantity of brick wall	448.50 sq.ft.
	Say	4.48 brass

|		
Item No.-2	Providing and casting in situ cement concrete m-15 of tap/granite/quartize/ gneiss metal for coping to plinth or parapit	
	Total length of wall	2x36'.6" =73.0 R.ft. 2x3x11.9 = 70.50 R.ft. 1x3.0 =3.0 R.ft. 1x10.0 = 10.0 R.ft. 1x5.0 = 5.0 R.ft.
	Deduction	1x10.0 = (-)7.0 R.ft.
	Shutter	1x10.0 = (-)10.0 R.ft.
		1x144.50x9"x4" = 36.0 cu.ft.
	Concrete pit for square pipe	16x1'.6"x9"x9"=13.50 cu.ft.
	Total	49.50 cu.ft.
	Net quantity of p.c.c m-15	49.50 cu.ft.
Item No.-3	Providing internal cement plaster 12mm thick in single coat in cement mortor 1:3 without Neeru finish to concrete or brick surface in all position including scaffolding and curring. Providing groove at joint of B.B. masonry and concrete members complete.	
	Shed long wall	2x (2x36.6x3.0) = 438.0 sq.ft.
	Shed short wall	2x (2x3x11.9x3.0) = 423.0 sq.ft.
	Varanda wall	2x (1x3.0x3.0) = 18.0 sq.ft. 2x (1x10.0x3.0) = 60.0 sq.ft. 2x (1x5.0x3.0) = 30.0 sq.ft.
	Steps	4x5.0x1.0 = 20.0 sq.ft.
	Top of wall	1x144.50x1.0 = 144.50 sq.ft.
	Total	1133.50 sq.ft.
	Deduction	2x (1x7'.0x3'.0) = 42.0 sq.ft. 2x (1x10'.0x3'.0) = 60.0 sq.ft.
		1031.50 sq.ft.
	Net quantity of plaster	1031.50 sq.ft. (Say 10.31 brass)

NOTE: -The quotation should be reach to this office by dated 03/09/2021 at 5.00 pm.

Head
Department of Vegetable Science
Dr. PDKV., Akola

CONDITIONS:

1. The quotation should be sent in sealed envelope.

2. On the left corner of envelope following matter should be clearly mentioned in block letters. **'Quotation for providing and constructing brick work, coping and plastering work of farm store** at Farm, Department of Vegetable Science, Dr. PDKV, Akola with reference to this office enquiry letter no. and date, HD/VS/Quot./   /2021, dated: 25/08/2021

3. Quotation should be send in the name of **Head, Department of Vegetable Science, Dr. PDKV, Akola** and address for correspondence is as undersigned.

4. The **CGST, SGST or Professional tax no.** must be mentioned in quotation letter.

5. The quoted price/rates should be 'all inclusive/exclusive' (i.e. GST & other expenses) as per guidelines of Govt. of India/Maharashtra.

6. Whatever GST applicable for the services, it should be mention separately in the final credit bill according to the billing proforma.

7. The payment of bill can only be made after satisfactory compliance of complete work/supply of materials and hence condition such as full or partial payment in advance, etc, are not acceptable.

8. The contractor should visit the site before submitting the quotations.

9. The incomplete details/specifications are liable to be rejected.

10. Time period for which the quotation will be valid should be clearly mentioned. Further the validity period should be up to **31 March 2022.**

11. Quotation received after last date will not be considered.

12. Conditional quotations are liable to be rejected.

13. The contractor should submit registration certificate of contractor-ship issued by competent authority should be attached with quotation.

14. The undersigned reserves full right to reject any or all quotation without assigning reasons thereof.

15. Authorization letter/ certificate in the support of the authorization contractor should be attached with the quotation.

16. The received sealed envelope quotations will be opened on **03/09/2021 at 5.30 pm.** in the chamber of undersigned in presence of staff members.

Head
Department of Vegetable Science
Dr. PDKV., Akola