



Department of Vegetable Science
Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola

No/HD/VS/Quot/Publish/ 309/2024-25

Dated: 14/07/2025

QUOTATION NOTICE

To,

1. Online publication
2. Notice board

Subject: - Supply the quotation for Extension of existing passage at Department of Vegetable Science, Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola 2025-26.


Please arrange to send quotation for Extension of existing passage at Department of Vegetable Science, Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola as per the particulars and conditions attached separately.

Note : The quotation should reach to this office by dated. 22/07/2025

Head
Dept. Vegetable Science
Dr. P.D.K.V., Akola

CONDITIONS :

1. The quotation should be sent in sealed envelope on the name of undersigned.
2. On the enveloped following should be clearly mentioned in block letters, **Quotations notice for Extension of existing passage at Department of Vegetable Science, Dr. PDKV, Akola 2024-25, Enquiry letter no. HD/VS/Quot./Publish/ 309 /2024-25, dated: 16/ 07/2025**
3. Price / rates should be 'exclusive of all GST/CST/VAT taxes and other expenses
4. The **GST/CST/VAT or Professional tax no.** must be mentioned on quotation letter.
5. **Civil contract certificate** must be attached with quotation.
6. **GST certificate, PTA certificate, PAN card and income tax return off last two years** must be attached with quotation.
7. Item available in ready stock and which can be supplied on placing firm order, may only be quoted.
8. The payment of bill can only be made after satisfactory compliance of complete supply/work and hence condition such as full or partial payment in advance, etc, are not acceptable.
9. Details specification, make, models, manufacturer, accessories, required. The quotation for the items for which rates a quoted. The incomplete details/ specification are liable to be rejected.
10. Time period for which the quotation will be valid should be clearly mentioned. Further the validity period should be up to **31st March, 2026.**
11. Quotation received after order date will not be considered.
12. Conditional quotations are liable to be rejected.
13. The undersigned reserves full right to reject any or all quotation without assigning reasons thereof.
14. Authorization letter/ certificate in the support of the authorization dealer of the company may be attached with the quotation.
15. The received sealed envelope quotations will be opened on **23/ 07 /2025 at 10.00 am.** in the chamber of undersigned in presence of staff members.


Head
Dept of Vegetable Science,
Dr. P.D.K.V., Akola

Name of Work : Extension of existing passage at Department Vegetable Science
PDSV, 2004



QUOTATION FOR

**NAME OF WORK : EXTENSION OF EXISTING PASSAGE AT
DEPARTMENT OF VEGETABLE SCIENCE, DR. PANJABRAO
DESHMUKH KRISHI VIDYAPEETH, AKOLA**


Name of Work: Extension of existing passage at Department Vegetable Science, Dr.
PDKV., Akola

"ABSTRACT SHEET"

S.N.	Qty.	Description of Items	Unit
1	6.00	Providing and lying cast in situ/Ready Mix Cement Concrete M-20 RCC single rim bored pile of 225 mm dia. each of load capacity as per design and of specified diameter of pile and bulb as directed, sunk to the required depth through all strata except rock, excluding provision of reinforcement including placing with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) by tremie arrangement, compaction of concrete including chipping and dressing including chipping and dressing if required etc. complete (Excluding steel reinforcement) S.S.R.I. NO. 22.01	Rmt.
2	2.95	Providing and lying Cast in situ/ Ready Mix Cement Concrete M-10 of trap/granite/quartzite/gneiss metal for foundation and bedding including bailing out water, steel centering, formwork, lying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) S.S.R. I. NO. 24.1	Cum.
3	0.28	Providing and laying Cast in situ/ Ready Mix Cement Concrete M-10 of trap/granite/quartzite/gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, lying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel) with fully automatic micro processor based PLC with SCADA enabled reversible Drum type mixer/concrete batch mix plant (Pan mixer)etc. complete with fine aggregate (Crushed sand VSI Grade) S.S.R. I. NO. 25.31	Cum.
4	0.86	Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete, (Excluding reinforcement and Structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc.	Cum.

		complete. With fine aggregate(Crushed sand VSI Grade) S.S.R. I. NO. 25.31	
5	0.516	Providing and fixing in position TMT-FE-500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. Including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete S.S.R. I. NO. 26.33	M.T.
6	0.83	Providing fly ash brick masonry with conventional /I.S. type fly ash bricks in C.M.1:6 in foundation and plinth including bailing out water manually striking joints, racking out joints watering and scaffolding etc. complete. S.S.R. I. NO. 27.12	Cum.
7	0.45	Providing fly ash brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete . S.S.R. I. NO. 27.13	Cum.
8	13.26	Filling in plinth and floors with contractors material /brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete. S.S.R. I. NO. 21.37	Cum.
9	4.82	Providing soling using 80mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete. S.S.R. I. NO. 21.40	Cum.
10	3.26	Providing internal cement plaster 20mm thick in Single coats in cement mortar 1:4 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete. S.S.R. I. NO. 32.7	Sq.m.
11	12.49	Providing and faced plaster externally in cement mortar using approved screened and, in all positions including base coat of 15 mm thick in cement mortar 1:4 using water proofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete S.S.R. I. NO. 32.11	Sq.m.
12	26.39	Providing and laying vitrified mirror /glossy finish tiles decorative type having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006(group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete. S.S.R. I. NO. 32.40	Sq.m.
13	4.02	Providing and laying vitrified mirror/glossy finish tiles having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS.15622-2006(group Bla) of approved make, shade and pattern for dado and skirting in required position fixed in 1:4 cement mortar including neat	Sq.m.

		cement float, filling joints, curing and clearing etc. complete. S.S.R. I. NO. 32.41	
14	12.49	Providing and applying two coats of exterior acrylic emulsion paint conforming to corresponding I.S. of approved manufacture and of approved colour to the plastered surfaces including cleaning, preparing the plaster surface, applying primer coat, scaffolding if necessary , and watering the surface for two days etc complete. S.S.R. I. NO. 35.25	Sq.m.
15	12.49	Providing and applying one coat of seal cement primer of approved manufacture and shed including scaffolding preparing the surface by cleaning dirt and other foreign matters, scrapping if necessary including scaffolding etc. complete. S.S.R. I. NO. 35.22	Sq.m.
			Total =
		Contingency	5% =
		GST	18% =
			Total Rs.=


 Head
 Dept. Vegetable Science
 Dr. P.D.K.V., Akola