



**Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola**  
**KRISHI VIGYAN KENDRA, SELSURA**  
**Post : Selsura, Dist. Wardha (M.S.)- 442 001**



Phone/Fax: (07152)287085

E-mail : [kvk.wardha@gmail.com](mailto:kvk.wardha@gmail.com)

NO. / KVK / Selsura / 2208/ 2025

Dated: 22/12/2025

**Quotation Notice**

To,

-----  
-----

Subject: Quotation for Providing Construction of Two implement shed with each one size (40×20) feet

Interested parties/suppliers are requested to submit quotation for the following on or before 29.12.2025 in office working days and the quotation will be open on the same day.

Sr. No.	Particulars	Qtn.	Rate	Unit	Amount
1	Providing and laying cast in situ/ Ready Mix Cement Concrete M-20 RCC single rim bored pile of 225 mm dia each of load capacity as per design and of specified diameter of pile and bulb as directed sunk to the required depth through all strata except rock excluding provision of reinforcement including placing with fully automatic micro processor based PLC with SCADA enabled reversible Drum type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) by tremie arrangement, compaction of concrete including chipping and dressing including chipping and dressing if required etc. complete (Excluding steel reinforcement).	12.00		Rmt	
2	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap /granite/quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel cementing formwork, cover blocks ,laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix (Pan mixer) etc. complete. With fine aggregate (Crushed Sand VSI Grade)	0.12		Cum	
3	Providing and laying cast in situ/Ready Mix cement concrete M-20 of trap / granite / quartzite/gneiss metal for	0.16		Cum	

*[Handwritten signature]*



3	R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying / pumping, compaction finishing the form surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc complete (Excluding reinforcement and structural steel) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Tyre mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (crushed sand VSI Grade)	0.16		Cum	
4	Providing and applying two coats of water proof cement paint of approved manufacture and of approved colour to be plastered surfaces including scaffolding if necessary, cleaning and preparing the surface, watering for two days etc. complete	1.47		Sqm	
5.	Providing and fixing in position TMT-FE-500 bar reinforcement of various diameters for R.R.C. pile caps, footings foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc as per detailed designs, drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.15		MT	
6	Providing and fabricating structural steel work in rolled section like joist, channel, angles, tees etc as per detailed design & drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position, making riveted/bolted/welded connections. Without connecting plates. Braces etc. & including one coat of anticorrosive over it & two coats of oil paint of approved quality & shade complete.	0.66		MT	
7	Providing and fixing colour coated Zinalume (R) AZ150 (min 150 gms/s.mt. total on each side) profiled sheets for roofing. The feed material in manufactured out of nominal 0.45 mm Base Metal thickness (BMT) (0.5 mm TCT), Hi-strength steel with min 550 MPa yield strength, metallic hot dip coated with Aluminium -Zinc alloy (55% aluminium 43.4% zinc 1.6% silicon) with COLORBOND (R) steel quality super durable polyester paint coat.	134.20		MT	


While quoting the prices, the instructions given below may please be noted carefully

- 1) On the envelope following should be clearly mentioned in block capital letters: Submitted to the Office of the Senior Scientist & Head, Krishi Vigyan Kendra, Selsura Dist. Wardha Quotation for

*Handwritten signature/initials*

“ Providing Construction work for Two Implement Shed (40 ×20)feet” Enquiry Letter No. KVK/Selsura/ 2298 /2025 Dt. 22.12.2025

- 2) Quotation should reach to this office on or before due date 29/12/2025
- 3) The quotation will have to be inclusive of all taxes (i.e. CGST & SGST) at KVK, Selsura Dist. Wardha (Dr.PDKV).
- 4) The undersigned reserves full right to reject any or all the quotations without assigning any reason Thereof or part of items.
- 5) The firm should have be registered GST Number should submit with quotation.
- 6) The material will have to be supplied as per specifications within 07 days from the date of issue of the supply order or as indicated in the order with warranty at KVK, Selsura.
- 7) In the event of failure to supply the material within the specified period, the undersigned will be authorized to cancel the order for supply.



Senior Scientist & Head  
Krishi Vigyan Kendra, Selsura