



**Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola**  
**KRISHI VIGYAN KENDRA, SELSURA**

**Post : Selsura, Dist. Wardha (M.S.)- 442 001**

**Phone/FAX:( 07152) 287085 E-mail : kvk.wardha@gmail.com**



NO. / KVK /Selsura / 1780 / 2024

Dated: 05/12/2024

**Quotation Notice**

To,

-----  
-----

**Subject:** Quotation for Supply of Construction of Fodder Storage Shed....

Interested parties/suppliers are requested to submit quotation for the Construction of Fodder Storage Shed (Size: 50 ft x 30 ft x 15 ft) on or before 12/12/2024 in office working days and the quotation will be open on the same day.

Sr. No.	PARTICULAS	QTN	UNIT	RATE	AMOUNT
1.	ITEM NO. 1 :- Excavation Excavation for foundation in earth soil of all types, sand, gravel & soft murum including removing the excavated material upto a distance 50 m beyond the building area & stacking & spreading as directed deawatering, preparing the bed for the foundation & necessary back filling, ramming, watering incl. shoring & shuttering etc. complete.	37	Cu.m		
2.	ITEM NO. 2 :- Plinth Filling Filling in plinth & floors with contractors soil, sand or murum in 15cm to 20cm layers inc. dewatering & compaction complete coloumn	84	Cu.m		
3.	ITEM NO.3 :- R.C.C Footing Providing & laying in situ cement concrete 1:2:4 of trap / granite / quartzite / gneiness metal footing & bedding including boiling out water manually farmwork, compacting & curing complete excl. mild steel.	7.2	Cu.m		
4.	ITEM NO. 4 :- R.C.C Coloumn Providing & laying in situ cement concrete M-15 of trap / granite / quartzite / gneiness metal for coloumn as per detailed drawing & design as directed incl. centring, framework, compaction & curing etc. complete Excl. steel.	4	Cu.m		
5.	ITEM NO. 5 :- R.C.C Beam Providing & laying in situ C.C M-15 of trap / quartzite / gneiness metal for beam & lintel as per detailed drawing & design as directed incl. centring, framework, compaction & curing etc. complete, Excl. steel.	5.4	Cu.m		
6.	ITEM No. 6 :- Reinforcement Providing & fixing in position HYSD steel MT bar as per instruction and drawing including cutting, bending and binfiling the wires or track welding, footing, foundation, beam, coloumn, etc.	1.00	Ton		

7.	ITEM No. 7 :- Brick Masonry – Providing second class burnt 09 inch thickness masonry with conventional / I.S. type bricks in cement mortar 1:6 in superstructure as backing in composite masonry incl. scaffolding, racking out joints, watering complete.	30	Cu.m		
<b>Total amount</b>		-			

While quoting the prices, the instructions on the overleaf may please be noted carefully

- 1) On the envelope following should be clearly mentioned in block capital letters : Submitted to the Office of the Senior Scientist & Head, Krishi Vigyan Kendra, Selsura Dist. Wardha Quotation for “Construction of Fodder Storage Shed” Enquiry Letter No.KVK/Selsura/ 1780 /2024 Dt. 05/12/2024.
- 2) Quotation should reach to this office on or before due date 12/12/2024.
- 3) The quotation will have to be inclusive all (i.e. **inclusive of all taxes, GST & transportation**) at KVK, Selsura Dist. Wardha (Dr.PDKV).
- 4) The undersigned reserves full right to reject any or all the quotations without assigning any reason Thereof or part of items.
- 5) The material will have to be supplied as per specifications of the supply order or as indicated in the order.
- 6) In the event of failure to supply the material, completion of work within the specified period, the undersigned will be authorized to cancel the order for work.
- 7) The Payment of bill will only be made after satisfactory compliance of complete order/work, and conditions such as full or partial payment in advance will not be acceptable.

  
 5/12/24  
**Senior Scientist & Head**