



**Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola**  
**KRISHI VIGYAN KENDRA, SELSURA**

**Post : Selsura, Dist. Wardha (M.S.)- 442 001**

**Phone/FAX:( 07152) 287085E-mail : [kvk.wardha@gmail.com](mailto:kvk.wardha@gmail.com)**



NO. / KVK /Selsura /2648/ 2026

Dated: 27/02/2026

**Quotation Notice**

To,

-----  
-----

**Subject:** Quotation for Renovating an old concrete structure and converting it into a dairy processing and feed storage unit....

Interested parties/suppliers are requested to submit quotation for the Renovating an old concrete structure and converting it into a dairy processing and feed storage unit on or before 06/03/2026 in office working days and the quotation will be open on the same day.

Sr. No.	Description Of Item	Quantity	Unit	Rate/ Unit In Rs.	Amount In Rs.
1	Providing and laying in situ/Ready Mix cement concrete in <b>M10 of trap/granite/quartzite/ gneiss metal for foundation and bedding</b> including bailing out water, formwork, compacting and curing complete, with fully automatic microprocessor-based PLC with SCADA enabled reversible Drum Type mixer,	16.300	Square Metre		
2	Providing and casting in situ/Ready mix cement concrete <b>M15 of trap/ granite/quartzite/gneiss metal for coping to plinth or parapet</b> , moulded or chamfered as per drawing or as directed including steel centering, plywood/steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed).	1.260	Cubic Metre		
3	Providing and laying machine cut machine Polished Kota stone flooring 25mm to 30mm thick and required width in plain/diamond pattern on bed of 1:6 C.M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning etc. complete.	61.000	Cubic Metre		
4	Providing and casting in situ/ready mix cement concrete <b>M20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns</b> as per detailed designs and drawing or as directed including centering, formwork, cover blocks compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel).With fully automatic microprocessor based PLC with SCADA enabled reversible drum type concrete mixer <b>With Natural sand.</b>	0.490	Cubic Metre		
5	Providing and fixing in position <b>TMT / Fe 500 bars reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams and columns, canopies, staircases, newels, chajjas, lintels, pardies, coping, fins, arches etc.</b> as per detailed design and drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed.	0.193	Metric Tonn		
6	Providing and fabricating <b>structural steel work in rolled section</b> like joist, channel, angles, tees etc. as per detail design & drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position, making riveted/bolted/ welded connections without connecting plates, braces etc. & including one coat of anticorrosive over it & two coats of oil paint of approved quality & shade complete.	0.500	Metric Tonn		

*Handwritten signature/initials*

7	Providing and fixing <b>G.I. pre-coated metacolour sheet of 0.50 mm thick and 930 profile for roof</b> including roof bolt and necessary fixing fixtures, arrangements (Prior approval of Sample and brand by Ex. Engineer is necessary before use).	117.050	Square Metre		
8	Providing and fixing <b>G.I. pre-coated metacolour sheet with accessories of 0.50 mm thick and 600 mm wide for ridge / valley</b> including roof bolt and necessary fitting arrangements (Prior approval of Sample and brand by Ex. Engineer is necessary before use).	15.300	Running Metre		
9	Providing <b>fly ash brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure</b> including striking joints, raking out joints, watering and scaffolding etc. Complete.	8.650	Cubic Metre		
10	Providing and fixing in position (as per 1868 / 1982) <b>Aluminium sliding window of two tracks</b> with rectangular pipe 95 x 38.10 x 0.90 mm at weight 0.637 kg/Rmt. with window frame bottom track section 92 x 31.75 x 1.30 mm at weight 1.070 kg/Rmt.. Top and side track section 92 x 31.75 x 1.30 mm at weight 0.933 kg/Rmt. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 kg/Rmt. and handle and top section 40 x 18 x 1.25 mm at weight 0.417 kg/Rmt. As per detailed drawings and as directed by Engineer in charge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass and aluminium mosquito net shutter with stainless steel jail with all required screws and nuts etc, complete. With powder coating with box.	2.250	Square Metre		
11	Jali welded mesh 50*25 13 Guage	52.880	Square Metre		
12	Providing and fixing M.S. grill door 24 Kilogram/One Square Metre of various size as per detailed drawings without hot dip coating, iron fixtures and fastenings and 3 coats of oil painting etc	12.600	Square Metre		
	Total Rs.				
	Add 18 % GST				
	Total Amount Rs.				

While quoting the prices, the instructions on the overleaf may please be noted carefully

- 1) On the envelope following should be clearly mentioned in block capital letters : Submitted to the Office of the Senior Scientist & Head, Krishi Vigyan Kendra, Selsura Dist. Wardha Quotation for "Renovating an old concrete structure and converting it into a dairy processing and feed storage unit" Enquiry Letter No.KVK/Selsura / /2026 Dt. 27/02/2026.
- 2) Quotation should reach to this office on or before due date 06/03/2026.
- 3) The quotation will have to be inclusive all (i.e. inclusive of all taxes, GST & transportation) at KVK, Selsura Dist. Wardha (Dr.PDKV).
- 4) The undersigned reserves full right to reject any or all the quotations without assigning any reason Thereof or part of items.
- 5) The material will have to be supplied as per specifications of the supply order or as indicated in the order.
- 6) In the event of failure to supply the material, completion of work within the specified period, the undersigned will be authorized to cancel the order for work.
- 7) The Payment of bill will only be made after satisfactory compliance of complete order/work, and conditions such as full or partial payment in advance will not be acceptable.



**Senior Scientist & Head  
Krishi Vigyan Kendra, Selsura**