



Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola
KRISHI VIGYAN KENDRA, SELSURA

Post : Selsura, Dist. Wardha (M.S.)- 442 001

Phone/FAX:(07152) 287085 E-mail : kvk.wardha@gmail.com



NO. / KVK /Selsura / 2902/ 2026

Dated:18/03/2026

Quotation Notice

To,

Subject: Quotation for Supply of Construction of Silage Unit

Interested parties/suppliers are requested to submit quotation for the Construction of Silage Unit (Size: 25 ft x 20 ft x 08 ft) on or before 24 /03 /2026 in office working days and the quotation will be open on the same day.

Sr. No.	PARTICULAS	QT N	RATE	UNIT	AMOUNT
1.	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 0.00 to 1.50 m.)	19.440		Cu.m	
2.	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. complete.	1.94		Cu.m	
3.	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, formwork, compacting and curing complete, with fully automatic micro processor based PLC without SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand.	1.30		Cu.m	
4.	Providing and laying in situ/Ready Mix cement concrete M20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, formwork, cover blocks compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, With fully automatic micro processor based PLC without SCADA enabled reversible drum type mixer /concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand.	3.38		Cu.m	
5.	Providing and casting in situ/Ready Mix cement concrete M20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including centering, formwork, cover blocks compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel).With fully automatic micro processor based PLC without SCADA enabled reversible drum type mixer / concrete Batch mix plant (Pan mixer) etc. complete. With Natural sand/V.S.I. quality Artificial Sand.(Without SCADA)	1.59		Cu.m	
6.	Providing & laying Cast in situ/Ready Mix cement concrete M20 of trap / granite /quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs & drawings or as directed including centering, formwork, cover blocks compaction & roughening the surface if special finish is to be provided & curing etc. complete. (Excluding reinforcement and structural	1.32		Cu.m	

R/S
18/03/2026

	steel). with fully automatic micro processor based PLC without SCADA enabled reversible Drum Type mixer/ concrete batch mix plant (pan mixer) etc. complete. With natural sand/V.S.I.quality Artificial Sand. (Without SCADA).				
7.	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15cm. to 20cm. including watering and compaction etc. complete.	11.66		Cu.m	
8.	Providing fly ash brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete			Cu.m	
9.	Providing and laying Cast in situ /Ready Mix cement concrete M15 of trap/ granite/ quartzite/ gneiss metal for coping to plinth or parapet, moulded or chamfered as per drawing or as directed including steel centering, plywood/steel formwork compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.)	0.44		Cu.m.	
10.	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.473		MT	
11.	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:5 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete.	51.05		Sq.m.	
12.	Providing internal cement plaster 20mm thick in two coats in cement mortar 1:5 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete.	55.94		Sq.m.	
13.	Providing and laying plain in situ / ready mix M-20 cement concrete of trap/ granite/ quartzite/ gneiss/ crushed stone metal mechanically mixed, placed in foundation and compacted by vibration including necessary bailing out water, curing curing concrete batch mix plant / pan mixer with Natural / VSI standard Artificial Sand) (excluding dewatering by pump) for 14 days, RCC Grade. With Concrete Mixer.	6.98		Cu.m.	
	Total amount	-			

While quoting the prices, the instructions on the overleaf may please be noted carefully

- 1) On the envelope following should be clearly mentioned in block capital letters : Submitted to the Office of the Senior Scientist & Head, Krishi Vigyan Kendra, Selsura Dist. Wardha Quotation for "Construction of Silage Unit" Enquiry Letter No.KVK/Selsura/ 2902 /2026 Dt. 18/03/2026.
- 2) Quotation should reach to this office on or before due date **24 /03 /2026**.
- 3) The quotation will have to be inclusive all (i.e. inclusive of all taxes, GST & transportation) at KVK, Selsura Dist. Wardha (Dr.PDKV).
- 4) The undersigned reserves full right to reject any or all the quotations without assigning any reason Thereof or part of items.
- 5) The material will have to be supplied as per specifications of the supply order or as indicated in the order.
- 6) In the event of failure to supply the material, completion of work within the specified period, the undersigned will be authorized to cancel the order for work.
- 7) The Payment of bill will only be made after satisfactory compliance of complete order/work, and conditions such as full or partial payment in advance will not be acceptable.


 18/3/2026
 Senior Scientist & Head
 Krishi Vigyan Kendra, Selsura