



Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola
KRISHI VIGYAN KENDRA, SELSURA

Post : Selsura, Dist. Wardha (M.S.)- 442 001

Phone/FAX:(07152) 287085 E-mail : kvk.wardha@gmail.com



NO. / KVK /Selsura / 93/ 2024

Dated: 25/ 04/2024

Quotation Notice

To,

Subject: Quotation for Supply of Construction of Sericulture Shed

Interested parties/suppliers are requested to submit quotation for the Construction of Sericulture Shed (Size: 22 ft x 50 ft) on or before 03/05/2024 in office working days and the quotation will be open on the same day.

PARTICULAS	QTN	RATE	QTY	AMOUNT
ITEM NO. 1 :- Excavation Excavation for foundation in earth soil of all types, sand, gravel & soft murum including removing the excavated material upto a distance 50 m beyond the building area & stacking & spreading as directed deawatering, preparing the bed for the foundation & necessary back filling, ramming, watering incl. shoring & shuttering etc. complete.	21.02		Cu.m	
ITEM NO. 2 :- P.C.C - 1 : 4 : 8 Providing & laying in situ cement concrete peel 1:4:8 of trap / granite/ quartzite / gneiness metal for foundation & bedding incl. boiling of water manually, formwork compacting & curing complete.	2.26		Cu.m	
ITEM NO. 3 :- Plinth Filling Filling in plinth & floors with contractors soil, sand or murum in 15cm to 20cm layers incl. dewatering & compaction complete coloumn	54.32		Cu.m	
ITEM NO. 4 :- R.C.C Footing Providing & laying in situ cement concrete 1:2:4 of trap / granite / quartzite / gneiness metal footing & bedding including boiling out water manually farmwork, compacting & curing complete excl. mild steel.	5.01		Cu.m	
ITEM NO. 5 :- R.C.C Coloumn Providing & laying in situ cement concrete M-15 of trap / granite / quatztite / gneiness metal for coloumn as per detailed drawing & design as directed incl. centring, framework, compaction & curing etc. complete Excl. steel.	2.71		Cu.m	
ITEM NO. 6 :- R.C.C for Beam Providing & laying in situ C.C M-15 of trap / quartzite / gneisness metal for beam & lintel asper detailed drawing & design as directed incl. centring, framework, compaction & curing etc.complete, Excl. steel.	3.05		Cu.m	

ITEM No. 7 :- R.C.C for Lintel Providing & laying in situ cement concrete 1:2:4 of trap / granite / quartzite / gneiss metal for chajjas as per detailed drawing and design as directed incl. centring, framework, compaction & curing etc. complete. Excl. Steel.	0.09		Cu.m	
ITEM No. 8 :- Reinforcement Providing & fixing in position HYSD steel MT bar reinforcement of various diameters for rec pile caps, footing, foundation, slab, beam, coloumn, canopies, staircase, chajja,lintel, arch, etc. as per detailed design, drawing & schedule including cutting, bending, hooking the bars, binding the wires,or tack welding, & supporting etc. complete.	1.086		Ton	
ITEM No. 9 :- Brick Masonry - Half brick thick Providing second class burnt 4.5 inch thick masonry with conventional / I.S. type bricks in cement mortar 1:6 in superstructure as backing in composite masonry incl. scaffolding, racking out joints,watering complete.	40.26		Sq.m.	
ITEM No. 10:- Plain Plaster – Inside/Outside Providing plain plaster externally in cement mortar of 12 mm thick layer in all position including base coat finishing the surface by taking out grains & curing, scaffoldings etc. complete.	32.08		Sq.m.	
ITEM No. 11 :- IPS Flooring Providing and laying IPS for flooring Ghattai in required positioning laid on bed of 1:4 cementmortar incl. neat cement float, all specials required curing cleaning etc. complete.	7.63		Cu.m.	
ITEM No. 12 :- Water Tank Size: 6 ft x 4 ft x 3 ft (LBH) Providing and laying IPS for flooring Ghattai inrequired positioning laid on bed, includind PCC, RCC, Bricks wall, Plaster inside and outside, HYSD Bars	75		Sq.ft.	
Total amount	-			

While quoting the prices, the instructions on the overleaf may please be noted carefully

- 1) On the envelope following should be clearly mentioned in block capital letters : Submitted to the Office of the Senior Scientist & Head, Krishi Vigyan Kendra, Selsura Dist. Wardha Quotation for "Construction of Sericulture Shed" Enquiry Letter No.KVK/Selsura/ /2024 Dt.
- 2) Quotation should reach to this office on or before due date 03/05/2024.
- 3) The quotation will have to be inclusive all (i.e. inclusive of all taxes, GST & transportation) at KVK, Selsura Dist. Wardha (Dr.PDKV).
- 4) The undersigned reserves full right to reject any or all the quotations without assigning any reason Thereof or part of items.
- 5) The material will have to be supplied as per specifications of the supply order or as indicated in the order.
- 6) In the event of failure to supply the material within the specified period, the undersigned will be authorized to cancel the order for supply.
- 7) The Payment of bill will only be made after satisfactory compliance of complete order, and conditions such as full or partial payment in advance will not be acceptable.



**Senior Scientist & Head
Krishi Vigyan Kendra, Selsura**