



NO. / KVK /Selsura 879/ 2024

Dated: 09 /08 /2024

**QUOTATION NOTICE**

**Subject:- Providing Water Supply Pipeline at KVK Selsura, Tah, Deoli, Dist Wardha (Additional Work)**

Sealed quotations are invited in the name of undersigned from authorised agencies so as to reach in this office on or before 16.07.2024 upto 5 pm for the following items


The quotation will be opened on the same date. The right to reject any or all quotation or to calling fresh quotations reserved by the undersigned without assigning any reason there on.

The rates should be quoted including all taxes (with GST) charges delivery site of work. Quotation received after the prescribed date will not be accepted. The item of work enquiry No. And due date quoted clearly and written on the top of the envelope. The delivery period be mentioned in the quotation rates should be written in figures and words clearly.

Sr. No.	Item of work	Qty.	Unit	Rate Quoted by	Amount
1	2	3	4	5	6
1	Providing and laying in trenches 50 mm dia. medium grade having embossed as ISI Mark galvanised iron pipes? of 5.17 kilogram/meter necessary fitting remaking good the demolished portion with filling trenches and with primer of anticorrosive oil paint, 2 coats including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	8.00	Rmt		
2	Providing and Laying cast in situ/Ready Mix cement concrete in m-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping. Compacting, roughening them of special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant ( Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	8.20	Cum		
3	Providing and fixing 160mm Saddle to 150mm dia Pipe for taking 50mm dia connection at upper level including necessary labour claches and excavation etc. complete as directed.	4.00	Nos		
4	Providing SDP MTA including labour charges for fixing it in position to attach sprinkler pipe etc. complete as directed.	4.00	Nos		



5	Engaging JCB for excavation / dismantling the old pipeline etc. complete as directed.	18.00	Hours		
6	Providing & Supplying Air Valves as per IS-14845 and MJP'S standard specifications double orifice type combined with screw down isolating valve, small orifice elastic ball 6.0 a)136-2021-22-50mm dia.	4.00	Nos		
7	Supply of C.I. Mechanical Compression Flanged/ Socket Tailpiece (Popularly known as ITM Flanged/Socket Tailpiece) suitable for making flanged connection with the plain barre of C.I. Spun Pipes (as per-IS – 1536 / 2001) and D.I.XII 1 a) /146-2021-22-150mm dia	3.00	Nos		
<b>Total Amount Rs.</b>					

  
**Senior Scientist & Head**  
**Krishi Vigyan Kendra, Selsura**