

PULSES RESEARCH CENTRE

Dr. PANJABRAO DESHMUK KRISHI VIDYAPEETH, KRISHI NAGAR,
AKOLA 444 104 (M. S.)

No. SRS/Pulses/QN/142/2026

Date: 03/06/2026

Quotation Notice

Subject: Quotation for the work of Ground Flooring (concrete) in Tin shed Godown at the field of Pulses Research Centre.

S. N.	Item	Quantity	Rate	Unit
1	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in Super Structure as backing in composite masonry including bailing out water manually, striking joints, faking out joints and watering etc Complete.	3.38	--	CuM
2	Filling in plinth and floors with contractors material/brought from out side and approved by Engineer in charge in layer in 15cm to 20cm layers including watering and compaction complete	54.72	--	CuM
3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/quartzite/ gneiss metal for foundation and bedding including balling out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, inishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	9.12	--	CuM
4	Providing and fixing in position TMTFE500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules, including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete	0.46	--	MT
5	Providing and laying cement concrete flooring 50 mm thick with M15 cement concrete laid to proper level and slope in alternate bays including compaction, filling joints, marking lines to give the appearance of tiles of 30 cm x 30 cm or other size laid diagonally /square etc finishing smooth (with extra cement) in any colour as directed and curing etc. complete. With Natural Sand Spec. No. Bd.M.6 P.N. 381	60.80	--	SqM
6	Providing internal cement plaster 20mm thick in a two coat in cement mortar 1:5 without neeru finish to concrete, brick surfaces in all positions including scaffolding and curing	15.13	--	SqM
7	GST Charges			
8	Royalty charges			CuM
Total				

Terms and conditions of supply:

1. The sealed quotation may be sent in the name of Senior Research Scientist, Pulses Research Centre, Dr. Panjabrao Deshmukh Krishi Vidyapeeth, Akola mentioning Quotation for the work of Ground Flooring (concrete) in Tin shed Godown at the field of Pulses Research Centre.
2. The quotation should reach to this office as per the specification, on or **before date 12/06/2026 at 3.00 pm**

3. The rates quoted will have to be inclusive of all taxes with delivery and work installation at this office / field.
4. The right to accept whole or part of the quotation or reject without assigning any reason is reserved with the undersigned.
5. The material should be supplied or work should be done as per specifications asked for with Eight Days for the date of acceptance of the quotation.
6. In the event of failure to supply the material or completion of work within specified period, the undersigned is authorized to cancel the order for supply.
7. Quotation will be accepted only on working days during 10.30am to 5.00pm.
8. The quantity required is subject to variation.
9. The above-mentioned quantity may be increased or decreased at the time of work order
10. After completion of work, bill submitted in triplicate
11. GST No should mentioned on quotations..


3/6/26
Senior Research Scientist
Pulses Research Centre,
Dr. PDKV, Akola

Copy fwcs to :

The Officer Incharge, ARIS Cell, Dr. PDKV, Akola with requested to upload the quotation notice on university website.

